


ADDENDUM NO. 4

TAYLOR ENGINEERING, INC.



**DREDGED MATERIAL MANAGEMENT
AREA BV-4B CONSTRUCTION**

**BREVARD COUNTY, FLORIDA
OCTOBER, 2022**



SUMMARY OF QUESTIONS AND RESPONSES

Contractor:

HDPE Pipe Pressure Test, Sec.33-40-00-3.3. Confirm 36” Dia. Pipe from E Inlet # SW01 to MH #SW04 is only required to be pressure tested up to Wedge Gate Valve.

Response:

E Inlet # SW01 to MH #SW04 is the only pipe segment that **will not** be required to be pressure tested. **All** other segments **will** require pressure testing.

Contractor:

Monitoring Wells, Sec. 01-50-80, Dwg. C-3. Are there (xy) Coordinates available?

Response:

A cad file will be provided with this addendum to include locations of nested wells.

Contractor:

Staging Area, Sec. 01-50-00. Is there a street address for DMMA?

Response:

No. Property description of location is provided in Section 01 11 00 – Summary of Work.

Contractor:

Settlement Plates, Sec. 31-23-00-3.3, Dwg. C-21. What is required height for Cap above Dike Crest?

Response:

2-inch minimum above embankment in accordance with “Settlement Plate Installation” detail on Sheet C-21 of Drawings.

Contractor:

Settlement Plates, Sec. 31-23-00-3.3, Dwg. C-21. Bid Schedule = 6 Ea, Dwg. C-10 show 7 Ea.

Response:

The Contractor shall install (7) settlement plates for construction in accordance with Drawings.

Contractor:

Blanket Drain – Filter Cloth, Dwg. C-18. Does Filter Cloth encompass the entire #7 Stone or only the first 6'-6" @ Toe as shown in Detail Section?

Response:

The first 6' – 6" as shown in Detail Section.

Contractor:

Stabilized Roadways, Sec. 00-41-63A. Can Owner change Bid Qty. from CY's to SY's in order to make Bids more Equal?

Response:

No. Place bids accordingly.

Contractor:

Riprap/Ditch Rubble, Sec. 35-42-37-2.1. Is Bedding Stone required under Ditch Rubble?

Response:

No. The typical ditch section includes Mirafi FW404 woven filter fabric with 3-6" Ø stone in accordance with Sheet C-8 of Drawings.

Contractor:

Endangered Species, Sec. 01-35-43-3.1.C. Is Atlantic Salt Marsh Shake still included since Pipeline to Intercoastal is not part of this contract?

Response:

Yes.

Contractor:

Endangered Species, Sec. 01-35-43-3.1.C. Is Contractor required to prepare a Gopher Tortoise Survey and Relocation (if necessary), if so, will Owner add a Line Item to Bid Schedule.

Response:

No. This work will be completed by the Owner.

Contractor:

Can Owner provide CAD file?

Response:

CAD files can be accessed at the following link with the following credentials. Please contact JBrumfield@tayloengineering.com if there are any difficulties accessing the information.

Account Name:

BV4BConstruction

Password:

Brevard11

Direct Link:

<https://ftp.tayloengineering.com/?u=BV4BConstruction&p=Brevard11>