

TAYLOR ENGINEERING, INC.



ADDENDUM NO.1

DMMA DU-2 AND SJ-1 SHORELINE IMPROVEMENTS;

DUVAL AND ST. JOHNS COUNTY,
FLORIDA
AUGUST 30, 2019



SUMMARY OF QUESTIONS AND RESPONSES

DU-2

1. **QUESTION:** At the DU-2 site, there was existing HDPE pipe on the ground. Is that pipe to be used within this project or is all pipe for this project to be purchased new?

RESPONSE: Contractor is to provide corrugated double wall HDPE pipe as specified. Pipe onsite is not corrugated double walled.

2. **QUESTION:** Is the replacement of the fence at DU-2 included in the project?

RESPONSE: The contractor will not be required to replace the fence. However, the contractor will be required to reinstall the fence in its current location prior to certification of substantial completion of the project. Re-installing the fence may require concrete to re-set fence posts, fence ties, and other fence parts. Contractor should bid accordingly.

SJ-1

3. **QUESTION:** Please confirm that any fill necessary for re-grading the existing access road to SJ-1 can be obtained from the SJ-1 dredge site.

RESPONSE: Yes, material may be obtained from the hatched area in Sheet C-4 of the drawings labeled "Borrow Area".

4. **QUESTION:** Will material from the access road ditches need to be removed from the site or can it be stockpiled somewhere onsite?

RESPONSE: Material from the ditches may be stockpiled onsite at a location approved by the engineer.

5. **QUESTION:** On the offloading pad plan, there is a note requiring "clean sand" with LBR 40. Are we allowed to use limerock, clay, or other stabilizer material to enhance the LBR value of the sand?

RESPONSE: An LBR 40 can typically be reached with clean sand when utilizing the appropriate compaction methods. If there is difficulty reaching an LBR 40 with clean sand, then limerock or other stabilizer material may be used at the engineer's approval to enhance the LBR value.

6. **QUESTION:** There are two typical sections for the access road. Are you able to quantify each section? Or provide some direction, such as percentage of one and percentage of the other? Looking for quantity of ditches to be regraded.

RESPONSE: No survey is available of the roadway. The Contractor shall estimate the quantity based on a site visit.

7. **QUESTION:** Is the burning of removed vegetation allowed?

RESPONSE: No. All cleared vegetation must be removed from the site and disposed of appropriately.