

SECTION 01 11 00

SUMMARY OF WORK

PART 1 - GENERAL

1.1 WORK COVERED BY CONTRACT DOCUMENTS

A. Project Description

1. This project (**APPENDIX A**) generally entails dredging approximately ~~99,440~~ 66,000 cubic yards of material from the Intracoastal Waterway (ICWW), St. Lucie County, Reach I of the project area and will include excavation of the ICWW channel to target elevations of ~~-14 feet mean lower low water (MLLW) (project depth of -12 feet and 2-foot allowable overdredge) north of the Fort Pierce Harbor Project and~~ -12 feet MLLW (project depth of -10 feet and 2-foot allowable overdredge) south of the Fort Pierce Harbor Project. In accordance with permit conditions, material shall be dredged via the use of a hydraulic dredge to remove all material (inclusive of all in-channel debris) feasible from the approximate ~~±13,700~~ 5,900-foot long dredge template. Dredged material shall be hydraulically pumped to a beach disposal area located just south of Fort Pierce Inlet.
2. **APPENDICES D and E** provide geotechnical and survey data, respectively. An electronic version (in CAD or XYZ format) of the survey is available upon request.

B. Work Schedule

1. Bid opening for this project is contingent on receipt of permit modifications from regulatory agencies. It is expected that permits will be received by March 216, 2017. Notice to Proceed will be issued within two ~~weeks-business days~~ of bid opening. The Contractor will have at least 75 calendar days from the Notice to Proceed to complete the project. All work must be complete and the contractor must be demobilized from the beach disposal area by May 31, 2017. Additional time will be allowed for demobilization of equipment from the river and non-beach project areas. Construction of the project is funded and administered by the Florida Inland Navigation District.

PART 2 - PRODUCTS (NOT APPLICABLE)

PART 3 - EXECUTION (NOT APPLICABLE)

--End of Section--

THIS PAGE INTENTIONALLY LEFT BLANK