



22 middleton street
nashville, tennessee 37210
tel: (615) 255-1854

March 30, 2020

Mayor Chad D. Graham
Bedford County
1 Public Square, Suite #101
Shelbyville, Tennessee 37160

American Institute of Architects
Tennessee Society of Architects
Construction Specifications Institute
American Correctional Association
National Council of Architectural
Registration Boards
United States Green Building Council

RE: PROGRAMING PHASE
JUVENILE JUSTICE CENTER RENOVATION
BEDFORD COUNTY, TENNESSEE

Dear Mayor Graham:

Following is the feasibility study for the future renovation of the existing Bedford county Workhouse located at 203 Lane Parkway, Shelbyville, TN 37160. This feasibility study focuses on converting the existing workhouse into a Juvenile Detention Center. Included below are tasks completed and attached are supporting documents which allow us to determine the costs of renovating the existing facility versus building a new facility.

Upon review and approval of this feasibility study and once the County decides to either renovate the existing facility or build a new facility, KSA will provide a fee proposal to complete all Architectural and Engineering services required to produce a set of Contract Bid Documents and Specifications. For reference we have included A/E fees for each option to allow you to better understand total project costs.

Cost Comparison:

All new 14,800 SF Construction without a commercial kitchen:

Construction Cost Estimate:	\$5,180,000
<u>A/E Fees (State Fee Formula (35/log P-1.15):</u>	<u>\$325,826</u>
Subtotal:	\$5,505,826

Renovate 16,218 SF of Existing County Work House (Commercial Kitchen to remain as is):

Construction Cost Estimate:	\$1,833,660
Owner Contingency Estimate:	\$ 183,366
<u>A/E Fees (State Fee Formula (35/log P-1.15)x1.25:</u>	<u>\$ 171,193</u>
Subtotal:	\$2,188,219

The following list is a status of the Tasks outlined in the original proposal:

- Task 1: As built survey: KSA has visited the site and measured and drawn the existing conditions to allow us to prepare this feasibility study.
- Task 2: KSA has created a preliminary floor plan that shows alterations of the existing building to accommodate Bedford County's needs and allows us to prepare the cost estimates. See attached floor plan.
- Task 3: KSA has met with DCS and Juvenile Services and verified that the preliminary floor plan in Task 2 meets the required standards.
- Task 4: KSA will meet with Bedford County Codes to review the proposed renovation to verify whether this renovation will trigger additional renovations.

Bedford County Planning and Zoning www.bedfordcountyttn.org › Office: 931.685.1336

The Bedford County Building Codes Department issues permits for the County Jurisdiction only – (area located outside of any city jurisdictions). However, according to City of Shelbyville the City will not be involved in the permit review process for County owned buildings within the City limits. For additional information and/or questions please contact City office at 931-684-9001 or by email to Bryan Stevens at bryan.stevens@shelbyvilletn.org. Bryan Stevens, Building & Codes Director. County owned buildings are up to the County on how they want to renovate it. The City will not be involved in the permit review process.

County Permit:

Bedford County has adopted the 2015 International Building Codes as a building standard for all construction activities. County Codes Department will provide a preliminary review based on the programmatic drawings and a more thorough review at the future Permit submission phase.

The State Fire Marshall's Office will review all Juvenile Detention facilities. This review occurs during the design phases.

- Task 5: Attached is the schematic cost estimate encompassing items in Tasks 2, 3, and 4.
- Task 6: A new facility located on County owned property adjacent to the new Justice Center would cost according to current cost trends approximately around \$350 per Square Foot or \$5,180,00.00, as of Spring 2020, for a 14,800 SF new facility.

This cost range assumes the moderately restrictive construction (masonry, security glazing, hollow metal doors, security hardware and electronics) typical in juvenile operations. These costs represent the costs of bricks and mortar alone.

If you have any questions, please call.

Sincerely,
KLINE SWINNEY ASSOCIATES

A handwritten signature in black ink, appearing to read 'B. Kline', with a long horizontal stroke extending to the right.

Bart Kline, AIA

8/4/20 Juvenile Study Session

2nd floor Courthouse @ 5 pm

Those in attendance: Chair, Julie Sanders , Greg Vick, Jeff Sweeney, Brian Farris, Robert Daniel, Sylvia Pinson, Linda Yockey, Kellee Smith, Nicole Cashion, Charles Rich, Don Embry, Chad Fletcher, Barry Bennett

PURPOSE:

To determine Bedford County's future planning for Juvenile Detention Services

PLAN A:

Continue to provide local Juvenile Detention services within Bedford County in current location with revised meal planning.

--Concerns with not enough beds

---Short term needs- need kitchen, better meal prep ability (2 hot meals per day required). Discussed possibility of school system assisting but that was ruled out.

---Decreased space for education especially with COVID restrictions

----Discussed possible plan to use space at Sheriffs office. Sweeney to investigate in next 90 days to see what we can do short term.

----Smith and Cashion felt we can handle current juveniles in current facility with very little problems.

PLAN B:

Continue to provide local Juvenile Detention Services within Bedford County, moving location to previous Workhouse location at estimated required cost of ????

(to be determined based on studies that have been completed)

---Proposed plan by Kline and Sweeney- would require at least 750K investment initially. More costs in coming years expected.

---Concerns by Farris with this being a bandaid and short term fix, due to building being older and not a long term solution.

---Most people present felt this is definitely a short term fix and might cost more in long run due to building being so old.

PLAN C:

Discontinue Local Juvenile Services- send out-

----Costs would exceed what we are currently spending, per preliminary numbers. This needs to be discussed further. There are currently 17 juvenile facilities in Tennessee, which is very limited. Transport costs would be expensive as well as cost of staffing to accompany juveniles. Also education would not be as good as what they are currently receiving with current services. Title I receives funds and provides education to juveniles.

Additional Plan D was discussed-

Placing a new Juvenile facility at jail / justice center location ,in future once we have the funds as long term solution.

At end of meeting, it was decided by all present that Sweeney will get with other appropriate people and see what we can do to use part of Sheriffs office for education purposes when space is needed at current facility. We will reconvene after further studies have been done to formulate details of short term plan. It is estimated by Sweeney that this will take approximately 90 days.

BEDFORD COUNTY JUVENILE DETENTION FACILITY COST COMPARISON

RENOVATE 203 LANE PARKWAY FACILITY

PROGRAM COMPARISON

- 1 Includes existing kitchen facilities to remain as is.
- 2 Estimate based off of 27 juvenile detainees.
- 3 Renovation of 16,218 SF

4

The following cost estimate assumes removal and replacement of all mechanical, plumbing, and electrical where existing is to be demolished.

BUILDING NEW FACILITY AT BEDFORD COUNTY JUSTICE COMPLEX

Assuming no new kitchen required. Meals to be delivered from adjacent Justice Complex.

New Building 14,800 SF 14,800 350 \$/sf \$5,180,000

DIVISION 01 – GENERAL AND SPECIAL CONDITIONS

DIVISION 01 – GENERAL AND SPECIAL CONDITIONS

1 ls 135000

\$135,000.00

DIVISION 02 – DEMOLITION

Basic Wall: 1W2 Int CMU 8"	1158 SF	3.00	\$3,474.00
Basic Wall: 1W5 Int - 3 5/8" Mt/Gyp Partition - 4 7/8"	3842 SF	3.00	\$11,526.00
DEMO OR RELOCATE EXISTING WATER CLOSETS	17 EA	200.00	\$3,400.00
DEMO OR RELOCATE EXISTING LAVATORIES	16 EA	200.00	\$3,200.00
DEMO EXISTING SHOWERS	7 EA	150.00	\$1,050.00
DEMO EXISTING VAULT 30 SF	1 EA	1000.00	\$1,000.00
DEMO EXISTING STORFRONT 91 SF X 4 = 364	364 SF	8.00	\$2,912.00
DEMOLISH LAUNDRY SHED INCLUDING MEP AND SLAB	400 SF	6.00	\$2,400.00
DEMOLISH EXISTING STORAGE SHED	600 SF	8.00	\$4,800.00
CUT OUT EXISTING CONCRETE SLAB AND TRENCH FOR NEW PLUMBING AND REPAIR SLAB	120 lf	30.00	\$3,600.00
Remove old sealants	500 lf	1.00	\$500.00
Roof Panel Demolition	16,218 SF	1.30	\$21,083.40
TOTAL DIVISION 02 – DEMOLITION			\$58,945.40

DIVISION 03 – CONCRETE

Exterior concrete slab for expanded outdoor recreation area	900 sf	6.00	\$5,400.00
TOTAL DIVISION 03 – CONCRETE			\$5,400.00

DIVISION 04 – MASONRY

Basic Wall: 1W2 Int CMU 8" 12" HIGH	5449 SF	15.50	\$84,459.50
Basic Wall: 1W2 Int CMU 8" INFILL	193 SF	20.00	\$3,860.00
TOTAL DIVISION 04 – MASONRY			\$88,319.50

DIVISION 05 – METALS

Misc.	1 ls	8000.00	\$8,000.00
TOTAL DIVISION 05 – METALS			\$8,000.00

DIVISION 06 – WOOD AND PLASTICS

06 41 16 Cabinetwork and Plastic Laminate - Allowance \$10,000		10000.00	\$10,000.00
MISC.	1 ls	8000.00	\$8,000.00
TOTAL DIVISION 06 – WOOD AND PLASTICS			\$18,000.00

DIVISION 07 – THERMAL AND MOISTURE PROTECTION

07 41 16 Roof - Add layer of metal screw-down \$6 or New Insulation/Standing seam \$8	16400 sf	10.00 \$/SF	\$164,000.00
R 20 New Wall Insulation - existing metal sandwich panel appears to have little or no insulation field verify. 520x16=8,320			
07 22 02 Roof Insulation R30	8320 sf	2.50 \$/SF	\$20,800.00
07 60 00 flashing and sheet metal reroof	16400 sf	2.00 \$/SF	\$32,800.00
07 72 36 Automatic Smoke Vent System	520 lf	6.00 \$/lf	\$3,120.00
07 90 00 Caulking and Sealants	1 ea	5000.00	\$5,000.00
Misc.	1000 lf	4.00 \$/lf	\$4,000.00
	1 ls	\$22,972.00	\$22,972.00
TOTAL DIVISION 07 – THERMAL AND MOISTURE PROTECTION			\$252,692.00

DIVISION 8 – DOORS AND WINDOWS

81 DOORS- 30 EXISTING TO REMAIN	51 ea	1200.00 \$/SF	\$61,200.00
Sky Lights W TUBE/CHASE	26 ea	1000.00	\$26,000.00
No contact Visitor Window	1 ea	7000.00	\$7,000.00
11 19 00 Security Glass and Glazing Interior	200 sf	60.00	\$12,000.00
11 19 00 Security Glass and Glazing Exterior existing replace	600 sf	40.00	\$24,000.00
12 19 00 Security Glass and Glazing Exterior new	56 sf	40.00	\$2,240.00
11 19 00 Non Contact Wire Mesh and Security Fasteners	656 sf	10.00	\$6,560.00
11 19 00 Woven-Rod Mesh for Security Gates	0 sf	\$0.00	\$0.00
DIVISION 8 – DOORS AND WINDOWS			\$139,000.00

DIVISION 9 – FINISHES

09 29 00 Basic Wall: IW5_Int - 3 5/8" MtI/Gyp Partition - 4 7/8"	630 sf	6.00	\$3,780.00
09 29 00 Basic Wall: IW6_Int - 6" MtI/Gyp Partition - 7 1/4"	1965 sf	6.25	\$12,281.25
Lay-in Ceilings			\$0.00
09 29 00 GYPSUM BOARD CEILINGS	9812 sf	2.75	\$26,983.00
09 67 23 RESINOUS FLOORING	7000 SF	6.00	\$42,000.00
09 91 01 PAINTING	14000 SF	13.00	\$182,000.00
	12000 SF	2.50	\$30,000.00
TOTAL DIVISION 9 – FINISHES			\$297,044.25

DIVISION 10 – SPECIALTIES

10 28 00 TOILET ACCESSORIES	1 ls	1000.00	\$1,000.00
10 44 13 FIRE EXTINGUISHERS	4 ea	100.00	\$400.00
DIVISION 10 – SPECIALTIES			\$1,400.00

DIVISION 11 – EQUIPMENT (Allowance)

11 19 00 DETENTION EQUIPMENT			
11 19 13 METAL DETECTORS			
DIVISION 11 – EQUIPMENT			\$100,000.00

DIVISION 12 – FURNISHINGS

NONE

DIVISION 14 – CONVEYING SYSTEM

NOT APPLICABLE

DIVISION 21 – FIRE PROTECTION

MODIFY EXISTING SYSTEM

16218 sf	1.50	\$24,327.00
DIVISION 21 – FIRE PROTECTION		\$24,327.00

DIVISION 22 - PLUMBING

Plumbing	16218 SF	5.00	\$81,090.00
Pre-fab Showers			\$0.00
Security Fixtures	12 ea	5500.00	\$66,000.00
DIVISION 22 - PLUMBING			\$147,090.00

DIVISION 23 - HVAC

	16218 sf	5.00	\$81,090.00
DIVISION 23 - HVAC			\$81,090.00

DIVISION 26 - ELECTRICAL

Electrical	16218 sf	9.00	\$145,962.00
DIVISION 26 - ELECTRICAL			\$145,962.00

DIVISION 27 - COMMUNICATIONS RACEWAYS

27 41 16 VIDEO VISITATION SYSTEM	1000 LF	6.00	\$6,000.00
DIVISION 27 - COMMUNICATIONS RACEWAYS			\$6,000.00

DIVISION 28 - ELECTRONIC SAFETY AND SECURITY

28 23 00 SECURITY AND CAMERA SYSTEM	34	750.00	\$25,500.00
DIVISION 28 - ELECTRONIC SAFETY AND SECURITY			\$25,500.00

DIVISION 31 - EARTHWORK

MISC. ADA CORRECTIONS	1 LS	30000.00	\$30,000.00
DIVISION 31 - Earth Work			\$30,000.00

DIVISION 32 - EXTERIOR IMPROVEMENTS

32 31 01 CANTILEVER SLIDING VEHICLE GATES - SECURITY 425/lf	2 EA	10000.00	\$20,000.00
32 31 02 EXTERIOR SECURITY GATES	3 EA	1500.00	\$4,500.00
32 31 17 SECURITY CHAIN LINK FENCE AND GATES	8664 SF	8.00	\$69,312.00
ADA Misc.	1 ls	\$9,381.20	\$9,381.20
DIVISION 32 - EXTERIOR IMPROVEMENTS			\$103,193.20

DIVISION 33 - UTILITIES

NONE

SUBTOTAL			\$1,666,963.35
10% Early Design Phase Contingency			\$166,696.34
CONSTRUCTION COSTS TOTAL			\$1,833,659.69

OWNER'S CONTINGENCY FUNDS FOR HIDDEN CONDITIONS PROGRAM CHANGES, ETC.			\$183,365.97
BUDGET SUBTOTAL			\$2,017,025.65

This estimate does not include Furniture, Fixtures, and Moveable Equipment (FEE), Fees, and other soft costs.

DATE: MARCH 30, 2020

**KLINE
SWINNEY
ASSOCIATES**
architecture + interior design + planning

STATE DCS MINIMUM STANDARDS FOR PHYSICAL PLANT

[illegible]

State of Tennessee
Building Council
Industrial Representative
Members
Industrial Representative
Council and General
Assembly of the


1111

SWINNEY ASSOCIATES
architecture + interior design + planning

ES + planning

PROGRAMMING PHASE/FEASIBILITY STUDY
FOR JUVENILE DETENTION FACILITY FOR
BEDFORD COUNTY

G1.02

 WEST ELEVATION

1 DEMOLITION PLAN

DEMIC

D1.01

PROJECT NO	2050
DATE	Issue Date
SHEET NO.	

REVISIONS:

DEMOLITION PLAN


PROGRAMMING PHASE/FEASIBILITY STUDY
FOR JUVENILE DETENTION FACILITY FOR
BEDFORD COUNTY

Education should have a direct or indirect impact on personal or professional behavior or performance, physical, mental, or emotional, or on the ability to acquire knowledge or skills.

**KLINE
SWINNEY
ASSOCIATES**
architecture + interior design + planning

22 middleton street nashville tennessee 37210

American Institute of Architects
United States Green Building Council
National Council of American-Soviet Friendship
Board
Construction Services and Materials
American Corporation Manager
Tennessee Society of Architects



EXISTING FACILITY
PROGRAM DEFICIENCIES

1. REQUIREMENT #15: NEITHER OUTDOOR RECREATION AREA PROVIDES MINIMUM DIMENSIONS OF 30' X 30'
2. ADA DEFICIENCIES INCLUDE:
A. _____
3. _____

MEANS OF EGRESS: USING OCCUPANT LOAD 14.15

SPACES WITH ONE EXIT OR EXIT ACCESS DOORWAY
MAXIMUM OCCUPANT LOAD OF SPACE = 10 PEOPLE
MAXIMUM CORRIDOR PATH OF EGRESS TRAVEL DISTANCE = 100 FEET

READ DEAD CORRIDORS

1.3 CONDITION: REINFORCING CONTROLLED DOOR RELEASE

MAX. DEAD END LENGTH

30 FEET

25 FEET

[illegible]

ARCHITECTURAL SITE PLAN

PROGRAMMING PHASE/FEASABILITY STUDY
FOR JUVENILE DETENTION FACILITY FOR
BEDFORD COUNTY

A1.00


PRODUCT NO.	2050
DATE	Issue Date
SHEET NO.	

**KLINE
SWINNEY
ASSOCIATES**

architecture + interior design + planning

American Institute of Architects
United States Green Building Council
National Council of Architectural Registration Boards
Construction Specifications Institute
American Consulting Engineers
International Society of Interior Designers

22 middleton street nashville, tennessee 37210




2 DAY LIGHTING INTO CELLS

NOTES:

1. THIS CONCEPT ENVISIONS MINIMAL RENOVATIONS FOR A TEMPORARY FACILITY UP TO 5-10 YEARS. THE DAYLIGHTING WOULD BE PROVIDED BY SECURE TUBE SKYLIGHTS.
2. QUOTES AND MANY PHASES BELOW COME FROM THE DOCUMENT JUVENILE ACCOUNTABILITY INCARCERATING BLACK CRIMINALS PROGRAM BULLETIN FROM THE U.S. DEPT. OF JUSTICE.

QUESTIONS:

1. IS THERE A NEED FOR A NON-CONTACT VISITING ROOM? YES
2. IS THERE A NEED FOR INTERVIEW ROOMS WITHIN OR IMMEDIATELY ADJACENT TO THE HOUSING UNIT? YES
3. IS THERE A NEED FOR ADDITIONAL STORAGE SPACE (per room, linen, and other items) AND SO ON WITHIN OR IMMEDIATELY ADJACENT TO THE HOUSING UNIT? YES
4. IS THERE A NEED FOR "TIMEOUT ROOMS"? YES
5. IS THERE A NEED FOR "GROUP LIVING SPACES" ADJACENT TO THE SLEEPING ROOMS? YES
6. IS THERE A NEED FOR SEPARATE/DECONTAINED COUNSELING SPACES? YES



SPATIAL RELATIONSHIP DIAGRAM FOR PARTIAL RENOVATION OF EXISTING FACILITY FOR SHORT TERM USE

LEGEND

- SECURE ACCESS CONTROL
- SECONDARY ACCESS CONTROL
- SECURE AREA
- VISIBILITY
- EXTERIOR ENVIRONMENT
- COMMUNICATION PORT

NOTES:
 *NO MORE THAN 20% SHOULD BE MULTIPLE OCCUPANCY ON INDIVIDUAL SLEEPING ROOMS

OCS STANDARDS
 (1) NO APPLICABLE AT THIS SITE.
 (2) NO APPLICABLE AT THIS SITE.
 (3) NO APPLICABLE AT THIS SITE.
 (4) NO APPLICABLE AT THIS SITE.
 (5) NO APPLICABLE AT THIS SITE.
 (6) NO APPLICABLE AT THIS SITE.
 (7) NO APPLICABLE AT THIS SITE.
 (8) NO APPLICABLE AT THIS SITE.
 (9) NO APPLICABLE AT THIS SITE.
 (10) NO APPLICABLE AT THIS SITE.
 (11) NO APPLICABLE AT THIS SITE.
 (12) NO APPLICABLE AT THIS SITE.
 (13) NO APPLICABLE AT THIS SITE.
 (14) NO APPLICABLE AT THIS SITE.
 (15) NO APPLICABLE AT THIS SITE.
 (16) NO APPLICABLE AT THIS SITE.
 (17) NO APPLICABLE AT THIS SITE.
 (18) NO APPLICABLE AT THIS SITE.
 (19) NO APPLICABLE AT THIS SITE.
 (20) NO APPLICABLE AT THIS SITE.
 (21) NO APPLICABLE AT THIS SITE.
 (22) NO APPLICABLE AT THIS SITE.
 (23) NO APPLICABLE AT THIS SITE.
 (24) NO APPLICABLE AT THIS SITE.
 (25) NO APPLICABLE AT THIS SITE.
 (26) NO APPLICABLE AT THIS SITE.
 (27) NO APPLICABLE AT THIS SITE.
 (28) NO APPLICABLE AT THIS SITE.
 (29) NO APPLICABLE AT THIS SITE.
 (30) NO APPLICABLE AT THIS SITE.
 (31) NO APPLICABLE AT THIS SITE.
 (32) NO APPLICABLE AT THIS SITE.
 (33) NO APPLICABLE AT THIS SITE.
 (34) NO APPLICABLE AT THIS SITE.
 (35) NO APPLICABLE AT THIS SITE.
 (36) NO APPLICABLE AT THIS SITE.
 (37) NO APPLICABLE AT THIS SITE.
 (38) NO APPLICABLE AT THIS SITE.
 (39) NO APPLICABLE AT THIS SITE.
 (40) NO APPLICABLE AT THIS SITE.
 (41) NO APPLICABLE AT THIS SITE.
 (42) NO APPLICABLE AT THIS SITE.
 (43) NO APPLICABLE AT THIS SITE.
 (44) NO APPLICABLE AT THIS SITE.
 (45) NO APPLICABLE AT THIS SITE.
 (46) NO APPLICABLE AT THIS SITE.
 (47) NO APPLICABLE AT THIS SITE.
 (48) NO APPLICABLE AT THIS SITE.
 (49) NO APPLICABLE AT THIS SITE.
 (50) NO APPLICABLE AT THIS SITE.
 (51) NO APPLICABLE AT THIS SITE.
 (52) NO APPLICABLE AT THIS SITE.
 (53) NO APPLICABLE AT THIS SITE.
 (54) NO APPLICABLE AT THIS SITE.
 (55) NO APPLICABLE AT THIS SITE.
 (56) NO APPLICABLE AT THIS SITE.
 (57) NO APPLICABLE AT THIS SITE.
 (58) NO APPLICABLE AT THIS SITE.
 (59) NO APPLICABLE AT THIS SITE.
 (60) NO APPLICABLE AT THIS SITE.
 (61) NO APPLICABLE AT THIS SITE.
 (62) NO APPLICABLE AT THIS SITE.
 (63) NO APPLICABLE AT THIS SITE.
 (64) NO APPLICABLE AT THIS SITE.
 (65) NO APPLICABLE AT THIS SITE.
 (66) NO APPLICABLE AT THIS SITE.
 (67) NO APPLICABLE AT THIS SITE.
 (68) NO APPLICABLE AT THIS SITE.
 (69) NO APPLICABLE AT THIS SITE.
 (70) NO APPLICABLE AT THIS SITE.
 (71) NO APPLICABLE AT THIS SITE.
 (72) NO APPLICABLE AT THIS SITE.
 (73) NO APPLICABLE AT THIS SITE.
 (74) NO APPLICABLE AT THIS SITE.
 (75) NO APPLICABLE AT THIS SITE.
 (76) NO APPLICABLE AT THIS SITE.
 (77) NO APPLICABLE AT THIS SITE.
 (78) NO APPLICABLE AT THIS SITE.
 (79) NO APPLICABLE AT THIS SITE.
 (80) NO APPLICABLE AT THIS SITE.
 (81) NO APPLICABLE AT THIS SITE.
 (82) NO APPLICABLE AT THIS SITE.
 (83) NO APPLICABLE AT THIS SITE.
 (84) NO APPLICABLE AT THIS SITE.
 (85) NO APPLICABLE AT THIS SITE.
 (86) NO APPLICABLE AT THIS SITE.
 (87) NO APPLICABLE AT THIS SITE.
 (88) NO APPLICABLE AT THIS SITE.
 (89) NO APPLICABLE AT THIS SITE.
 (90) NO APPLICABLE AT THIS SITE.
 (91) NO APPLICABLE AT THIS SITE.
 (92) NO APPLICABLE AT THIS SITE.
 (93) NO APPLICABLE AT THIS SITE.
 (94) NO APPLICABLE AT THIS SITE.
 (95) NO APPLICABLE AT THIS SITE.
 (96) NO APPLICABLE AT THIS SITE.
 (97) NO APPLICABLE AT THIS SITE.
 (98) NO APPLICABLE AT THIS SITE.
 (99) NO APPLICABLE AT THIS SITE.
 (100) NO APPLICABLE AT THIS SITE.

SPATIAL RELATIONSHIPS DIAGRAM "B"

PROGRAMMING PHASE/FEASIBILITY STUDY FOR JUVENILE DETENTION FACILITY FOR BEDFORD COUNTY

KLINE SWINNEY ASSOCIATES
 architecture + interior design + planning

22 middleton street nashville, tennessee 37210

A1.01b

PROJECT NO. 2020
 DATE: 2020
 SHEET NO. 1



	SECURE ACCESS CONTROL.
	SECONDARY ACCESS CONTROL.
	SECURE AREA.
	VISIBILITY.

SECURE ACCESS CONTROL

SKY LIGHT

SEE DCS STANDARDS ON SHEET G1 02

COMMUNICATIONS PORT


EAST
ELEVATION

PROGRAMMING PHASE/FEASABILITY STUDY
FOR JUVENILE DETENTION FACILITY FOR
BEDFORD COUNTY


PROJECT NO.	2050
DATE	Issue Date
SHEET NO.	

**KLINE
SWINNEY
ASSOCIATES**
architecture + interior design + planning


22 middleton street nashville, tennessee 37210



THREE PERSON SLEEPING ROOM
3 SP.135
1/2" = 1'-0"



TWO PERSON SLEEPING ROOM PLAN
2 SP. 133
1/2" = 1'-0"



TWO PERSON ACCESSIBLE SLEEPING ROOM PLAN
1 SP. 132
1/2" = 1'-0"

(5) Multiple sleeping rooms shall not be designed to accommodate more than eight (8) youth. A minimum of thirty-five (35) square feet of unencumbered floor space for each youth shall be provided in such sleeping areas, with a ceiling height of not less than eight (8) feet. One wall measurement shall be at least seven (7) feet.

Each room shall contain a bunk, a toilet and a lavatory.


NOTE:

AS CURRENTLY DESIGNED THESE ROOMS ONLY HAVE ENOUGH ROOM FOR BUNKS, TOILET AND LAVATORY. IF ADDITIONAL FURNISHINGS ARE PROVIDED THEN ROOMS WILL NEED TO BE BIGGER OR NUMBER OF OCCUPANTS REDUCED. OWNER SHALL PROVIDE DESIGNER LIST OF FURNISHING TO BE PROVIDED AND THE DIMENSIONS.

LIST OF FURNISHINGS:

ITEM:
BUNK(S)

SIZE:
28" X 81"



FOUR PERSON SLEEPING ROOM PLAN
4 SP.143
1/2" = 1'-0"

NO.	DESCRIPTION

LARGE SCALE PLANS
PROGRAMMING PHASE/FEASIBILITY STUDY
FOR JUVENILE DETENTION FACILITY FOR
BEDFORD COUNTY

PROJECT NO.	2020
DATE	Issue Date
SHEET NO.	


A4.01

KLINE SWINNEY ASSOCIATES
architecture + interior design + planning

22 Middleton Street Nashville, Tennessee 37210

Architect's Seal of Professional Responsibility
I, the undersigned, being a duly licensed Architect under the laws of the State of Tennessee, do hereby certify that I am the Architect of the above described project and that I am a duly licensed Architect under the laws of the State of Tennessee.
Date: 10/1/2020
Signature: [Signature]

1 Section 3
1/8" = 1'-0"



PROJECT NO.
DATE
ISSUE DATE
SHEET NO.

A6.01

SECTIONS

PROGRAMMING PHASE/FEASIBILITY STUDY
FOR JUVENILE DETENTION FACILITY FOR
BEDFORD COUNTY

SECTION 3
1/8" = 1'-0"

**KLINE
SWINNEY
ASSOCIATES**
architecture + interior design + planning

22 middleton street nashville, tennessee 37210

Architect: Kline Swinney Associates, Inc.
Project: Bedford County Juvenile Detention Facility
Project No.: 09-01
Drawing No.: A6.01
Drawing Date: 3/18/2009
Drawing Title: Section 3
Drawing Scale: 1/8" = 1'-0"

LEGEND

- VISITORS
- ADMINISTRATION
- BUILDING SUPPORT
- JUVENILE SUPPORT
- JUVENILE EDUCATION
- JUVENILE RECREATION
- JUVENILE DETENTION


SCOPE

PROVIDE FLOOR PLANS, ELEVATIONS, AND ANTICIPATED CONSTRUCTION COSTS. THE DRAWINGS WILL BE USED TO PRESENT THE COMMISSION THE PROPOSED PROJECT. FOLLOWING ARE THE ITEMS TO BE INCLUDED IN THE DRAWINGS:

- ISOLATION ROOM FOR BEHAVIORAL ISSUES
- TWO (2) CELLS FOR MIDDLE SCHOOL AGED CHILDREN THAT EACH ACCOMMODATES 2 TO 3 STUDENTS
- ONE (1) EDUCATION ROOM THAT ACCOMMODATES 5 TO 8 STUDENTS
- ONE (1) JUVENILE DETENTION ROOM THAT ACCOMMODATES 10 TO 15 STUDENTS
- ONE (1) KITCHENETTE/RECREATION ROOM FOR EMPLOYEES
- SERVICE BAYLOADING DOCK

OTHER SPACE REQUIREMENTS FROM TN STATE DCS STANDARDS

- (3) The following minimum provisions shall be made by each facility:
 - (a) Sleeping areas shall be free from hazardous conditions that would facilitate suicide.
 - (b) All sleeping and activity areas shall have lighting of at least twenty (20) foot-candles to be measured three (3) feet off the floor.
 - (c) Sleeping areas shall have access to natural light in sleeping areas.
 - (d) Facilities shall maintain a temperature between sixty-five (65) degrees Fahrenheit and eighty (80) degrees Fahrenheit in sleeping and activity areas.
- (7) New Juvenile Detention Centers shall have a dayroom for each cluster of rooms. The dayroom shall offer a minimum of forty-five (45) square feet of floor space per youth. Existing facilities are not required to provide dayrooms.
- (9) Facilities shall have at least one (1) accessible shower for each cluster (15) detained youth, which shall be accessible to youth without having to leave their designated area.
- (10) New Juvenile Detention Centers shall provide a space inside the security perimeter, which shall be accessible to youth, for the purpose of receiving and discharging of youth received and discharged from the facility. This space shall have the following components:
 - (a) Preparationally room, accessible youth to use.
 - (b) Temporary holding rooms which have fixed benches to seat youth, and (c) shower, toilet, and washbasin.
- (12) Provision shall be made for visitation areas.
- (13) Provision shall be made for a private room to allow for discussions between clergy, attorneys and others authorized by the juvenile court.
- (15) Each new facility shall provide a secure outdoor recreation area with dimensions of at least 100 feet by 100 feet and an outdoor recreation area at the facility dimensions which has access to natural light.
- (17) Every Juvenile Detention Center shall have a secure control center, staffed continuously, through which telephones and other communications are channelled. The control center shall have direct access to the detention area and shall have the capability of monitoring service. This control center shall monitor the operation of security and life safety systems.



10,488 SQ. FT. GROSS
1 CONCEPTUAL FLOOR PLAN
100' x 100'


FLOOR PLAN - DIMENSIONED
BEDFORD COUNTY JUVENILE DETENTION CENTER
Enter address here
T80

REVISIONS

PROJECT NO.	19502
DATE	Issue DATE
PROJECT NAME	34-011-00
A1.01d	



1 MASSING VIEW



2 CUT PLANE ORTHO VIEW



10,443 SF

1 CONCEPTUAL FLOOR PLAN 1/8" = 1'-0"

SCOPE

PROVIDE FLOOR PLANS, ELEVATIONS, AND ANTICIPATED CONSTRUCTION COSTS. THE DRAWINGS WILL BE USED TO PRESENT THE COMMISSION THE PROPOSED PROJECT AND TO OBTAIN FINANCING FOR THE PROJECT. FOLLOWING ARE THE ITEMS TO BE INCLUDED IN THE DRAWINGS:

- SICK ROOM
- ISOLATION ROOM FOR BEHAVIORAL ISSUES
- TWO (2) CELLS FOR MIDDLE SCHOOL AGED CHILDREN THAT EACH ACCOMMODATES 2 TO 3 STUDENTS
- ONE (1) EDUCATION ROOM THAT ACCOMMODATES 5 TO 6 STUDENTS
- ONE (1) KITCHENETTE/REAROOM FOR EMPLOYEES
- ONE (1) KITCHENETTE/REAROOM FOR EMPLOYEES
- SERVICE BAYLOADING DOCK

OTHER SPACE REQUIREMENTS FROM TN STATE DCS STANDARDS

- (3) The following minimum provisions shall be made by each facility:
 - (a) Sleeping areas shall be free from hazardous conditions that would facilitate suicide.
 - (b) All sleeping and activity areas shall have lighting of at least twenty (20) foot-candles to be maintained three (3) feet of the floor.
 - (c) Sleeping areas shall have access to natural light in sleeping and activity areas.
 - (d) Facilities shall maintain a temperature between sixty-five (65) degrees Fahrenheit and eighty (80) degrees Fahrenheit in sleeping and activity areas.
- (7) New Juvenile Detention Centers shall have a dayroom for each cluster of rooms. The dayroom shall be a minimum of 100 square feet of floor space per youth. Existing facilities are not required to provide dayrooms.
- (9) Facilities shall have at least one (1) operable shower for every sixteen (16) detained youth which shall be accessible to youth without having to leave their designated area.
- (10) New Juvenile Detention Centers shall provide a secure outdoor recreation area, received and discharged from the facility. This space shall have the following requirements:
 - (a) Recreation only portion of the area shall be enclosed by a fence.
 - (b) Temporary holding rooms which have lined benches to seat youth; and
 - (c) Shower, toilet, and washbasin.
- (12) Provision shall be made for visitation areas.
- (13) Provision shall be made for a private room to allow for discussions between clergy, attorneys and others authorized by the juvenile court.
- (15) Each new facility shall provide a secure outdoor recreation area with dimensions of at least 100 feet by 50 feet. Existing facilities shall provide a secure outdoor recreation area with dimensions which has access to natural light.
- (17) Every Juvenile Detention Center shall have a secure control center, staffing community, through which inmates and staff shall be monitored. The control center shall monitor the operation of security and fire safety systems.

March 1, 2022 Meeting to discuss Juvenile Services

Those in attendance: Julie Sanders, Jeff Sweeney, Charles Rich, Nicole Cashion, Kellee Smith, Robert Daniel, Lori Schuler, Nakia Elliott

Juvenile Detention Center – keeping In Bedford County

- 11 staff, 1 director, 4 sergeants, 6 officers
- Nurse used from jail
- 2 hot meals per day
- Meals- from jail- costs added to juvenile budget- approx. \$500/month
- DCS pays 139\$ per day
- Rate changes to be considered
- Must transport Bedford County juveniles (only) for court, evaluations, Dr appts
- Cost estimate- \$275-\$324 per Bedford County Juvenile
- Approximately 200 Bedford County juveniles are taken in per year

1 staff= 16 sleeping, or 8 awake (Staff : juvenile ratio)

Sending Juveniles out of county

- Must have a 72 hour hold location- unsure of minimum square footage?? and must be supervised during this time
- While waiting on bed- must have 1 officer or more depending on male / female
- 6 officers- multiple shifts @ 55K per officer
- Transports required for each court appearance, evaluations, Dr appointments (there is a minimum of 3 transport trips for each juvenile before the actual booking)
- Gas costs
- 1 director
- Costs per child 150-175 per day minimum to send out (Rutherford 175, Putnam 150)
- Will need same amount of staff

Juvenile Detention Center

Historical Data:

2020-2021 - # of juveniles	163
2020-2021 - # of bed days	1,436
2021-2022 - # of juveniles	299
2021-2022 - # of bed days	2,954
YTD FY23 - # juveniles	215
YTD FY23 - # of bed days	2,237

Assumptions:

Estimated juveniles	200
Estimated bed days	1,600
Estimated cost per day at another facility	\$ 175
Estimated number of trips made per juvenile	4
Estimated mileage per round trip	49
Estimated cost of full-time transport officer	\$ 64,278
Estimated cost per mile	\$ 1.00

Rutherford County

24.6 miles each way
 Juvenile Guard base pay: \$39,266. Jail Guard base pay: \$39,266. Deputy base pay: \$50,735
 10.86% matching benefits, \$7,056 annual health, Workers Comp \$906, Life Insurance \$71

Projected Cost of Utilizing Another County's Juvenile Detention Facility:

Cost of Bed Days (\$175x1,600)	\$ 280,000	
Transportation Cost 200 kids, 4 trips each, 49 mi/trip, \$1/mile	39,360	
2 Full-time transport officers	128,556	Deputies
Projected Cost	\$ 447,916	

Cost per juvenile based on projection

Projected cost	\$ 447,916
Estimated juveniles	200
Cost per juvenile	\$ 2,240

Cost per bed day based on projection

Projected cost	\$ 447,916
Estimated bed days	1,600
Cost per bed day	\$ 280

FY23 YTD Actual Cost of Bedford County Juvenile Detention Facility:

As of March 31, 2023	
FY23 YTD Revenues	\$ 285,058
FY23 YTD Expenditures	(476,528)
FY23 YTD Expenditures in excess of Revenues	\$ (191,470)
Cost per juvenile based on actual revenues/expenditures	
FY23 YTD Expenditures in excess of Revenues	\$ (191,470)
FY23 YTD Juveniles	215
Cost per juvenile	\$ 891
Cost per bed day based on actual revenues/expenditures	
FY23 YTD Expenditures in excess of Revenues	\$ (191,470)
FY23 YTD bed days	2,237
Cost per bed day	\$ 86

Juvenile Detention
March 31, 2023

FY23 YTD	County																Juvenile Detention Expenditures by Year		Expenditures in Excess of Revenues	
	DCS	Coffee County	Franklin County	Grundy County	Lincoln County	Lewis County	Marshall County	Montgomery County	Moore County	Sequitah County	Sumner County	Warren County	Wilson County	General Sections	Traffic School	Receipts by Revenue Code	Total Receipts	Juvenile Detention Expenditures by Year	Expenditures in Excess of Revenues	
42450	192,567.12	34,800.00	2,030.00	1,675.00	14,266.00	-	2,320.00	2,755.00	290.00	-	3,625.00	725.00	1,305.00	-	26,700.00	256,358.12	285,058.12	476,527.84	(191,469.72)	
42450-15																		Budget - \$697,568		
FY22																				
42450	223,147.80	26,136.00	2,244.00	-	32,472.00	-	1,320.00	12,276.00	-	-	1,452.00	-	-	-	32,900.00	299,047.80	331,947.80	535,711.86	(203,764.06)	
42450-15																				
FY21																				
42450	180,949.40	26,776.00	-	-	12,276.00	264.00	1,716.00	20,460.00	-	-	-	-	-	84.78	21,360.00	244,526.18	265,886.18	537,724.82	(271,838.64)	
42450-15																				
FY20																				
42450	163,224.54	4,092.00	-	-	17,292.00	-	1,584.00	-	-	-	-	-	-	-	28,640.00	186,192.54	215,032.54	524,048.60	(309,016.06)	
42450-15																				
FY19																				
42450	133,571.42	3,828.00	-	-	20,724.00	-	3,564.00	-	-	4,224.00	-	-	-	-	40,495.00	165,911.42	206,406.42	461,859.19	(255,452.77)	
42450-15																				
FY18																				
42450	146,279.50	9,900.00	-	-	39,072.00	132.00	2,640.00	-	-	-	-	-	-	99.75	67,955.00	196,123.65	266,078.65	450,751.18	(184,672.53)	
42450-15																				
FY17																				
42450	118,081.45	9,377.00	-	-	24,948.00	-	10,956.00	-	-	-	-	-	-	-	49,980.00	163,357.45	213,337.45	460,817.40	(247,479.95)	
42450-15																				
	1,157,821.63	116,904.00	4,274.00	1,675.00	161,050.00	396.00	24,100.00	35,491.00	290.00	4,224.00	5,077.00	725.00	1,305.00	184.53	270,210.00	1,783,747.16	1,783,747.16			

Juvenile Detention Center

April 2023



Building Pictures/Condition/Work Orders



Front office floor



Typical holding cell




Restroom 1



Restroom 2



Shower



Ceiling tile above metals ceiling grate is pretty rough.



Fire Alarm System

The Fire Alarm system needs to be upgraded soon. The current system is out of date and is difficult to find parts for.

The Roof

I don't have a picture of the roof however we believe the roof to be 20 years plus. I believe a new roof for this building would run approximately \$150,000-\$200,000.

The Plumbing

The overall plumbing in this building is in bad shape; fixtures and drains. We are constantly fighting sewer backups and leaks in the system.

Electrical

Lots of old wiring that will need to be updated in the future.


Doors and Hardware

There are a lot of issues with the doors and hardware...some upgrades need to happen for security and functionality.

Work Orders July 2021- March 2023

Group	Hvac	Hrs	Plumbing	Hrs	Electrical	Hrs	P.M	Hrs	Total W.O	Total Hrs
Totals	3	6.5	34	69.25	20	35	16	21.5	73	132.25

Juvenile Det. W.O's



Status	Requested	W.O #	Group	Hours	Location/Description	Completed	Assigned to
Juvenile Detention - July 2021-April 2023							
Closed	7/6/2021	4 P.M	3 hrs		mow yard - juvenile detention	7/2/2021	others
Closed	7/27/2021	80 Electrical	5 hrs		juvenile detention exit room replace bulb	7/27/2021	Tim/others
Closed	7/13/2021	37 Plumbing	1 hr		juvenile detention check for water leak	7/13/2021	Tim/others
Closed	8/16/2021	177 Plumbing	5 hrs		juvenile det all toilets stopped up	8/17/2021	others
Closed	8/16/2021	180 Hvac	4.5 hrs		juvenile probation unit not working	8/16/2021	Others
Closed	8/20/2021	191 P.M	2 hrs		juvenile det fix broken drain covers	8/24/2021	Rose
Closed	8/20/2021	193 P.M	2 hrs		juvenile dent get hose and pressure washer	8/24/2021	Rose
Closed	8/25/2021	196 Plumbing	3.5 hrs		juvenile detention employee rr toilet overflowing	8/25/2021	others
Closed	9/10/2021	234 Plumbing	3.5 hrs		juvenile detention cell bravo sewage backing up	9/10/2021	Others
Closed	9/13/2021	236 Plumbing	.75 hrs		juvenile detention cell bravo repaired toilet	9/10/2021	Tim/others
Closed	9/16/2021	252 Plumbing	3 hrs		juvenile detention toilet stopped up	9/16/2021	Tim/Others
Closed	9/16/2021	253 Plumbing	4 hrs		juvenile detention toilet keeps running	9/16/2021	Tim/others
Closed	9/17/2021	258 Plumbing	6 hrs		juvenile det. A pod sink stopped up	9/17/2021	Tim/Others
Closed	9/17/2021	259 Plumbing	4 hrs		juvenile det. A pod sink wont stop running	9/17/2021	Tim/others
Closed	9/17/2021	260 Plumbing	0 hrs		juvenile det. A toilet won't flush	9/17/2021	Tim/others
Closed	9/17/2021	261 Plumbing	0 hrs		juvenile det. B pod toilet not flushing	9/17/2021	Tim/others
Closed	9/17/2021	262 Plumbing	4 hrs		sewage backing up	9/17/2021	tim/darrell/j.w
Closed	9/27/2021	286 Plumbing	5.5 hrs		juvenile det. Bravo toilet not flushing	9/28/2021	Tim/others
Closed	10/15/2021	341 Electrical	3 hrs		back of juvenile det. Run power to network cage	10/15/2021	Rose/others
Closed	10/26/2021	361 Plumbing	1 hr		juvenile det shower pipe leaking	10/26/2021	Rose/Tim
Closed	10/27/2021	368 P.M	2 hrs		juvenile det. Help with salyport door	10/28/2021	Rose
Closed	12/8/2021	458 Plumbing	1.5 hrs		juvenile detention issues with toilet in one of the cells	12/9/2021	Rose/Tim/Jason
Closed	12/9/2021	463 Electrical	1 hr		juvenile detention changed lights	12/9/2021	Tim/rose/Jason
Closed	12/9/2021	458 Plumbing	1.5 hrs		juvenile detention issues with toilet in one of the cells	12/9/2021	Rose/Tim/Jason
Closed	12/9/2021	463 Electrical	1 hr		juvenile detention changed lights	12/9/2021	Tim/rose/Jason
Closed	12/9/2021	635 Plumbing	1 hr		juvenile det. Starter button not working	4/4/2022	Tim L
Closed	3/4/2022	827 Plumbing	1 hr		juvenile detention booking/shower area toilet leaking	5/24/2022	Tim L
Closed	5/20/2022	26 Electrical	1 hr		juvenile detention - dryer keeps tripping the breaker	7/15/2022	Tim L
Closed	7/15/2022	75 P.M	5 hrs		flag pole - need someone to look at it (juvenile detention)	8/10/2022	Tim L
Closed	8/9/2022	85 Plumbing	5 hrs		juvenile detention - sink in one of the cells is not draining	9/1/2022	Tim L
Closed	8/18/2022	108 P.M	1 hr		juvenile det-dryer not working again	9/8/2022	Tim/Evan
Closed	9/7/2022	113 P.M	1 hr		juvenile det- cell b having issues with the door and button	9/8/2022	Tim/Evan
Closed	9/7/2022	113 P.M	1 hr		juvenile detention - dryer keeps tripping the breaker	7/15/2022	Tim L
Closed	7/15/2022	26 Electrical	1 hr		flag pole - need someone to look at it (juvenile detention)	8/10/2022	Tim L
Closed	8/9/2022	75 P.M	5 hrs		juvenile detention - sink in one of the cells is not draining	9/1/2022	Tim L
Closed	8/18/2022	85 Plumbing	5 hrs		juvenile detention - dryer not working again	9/8/2022	Tim/Evan
Closed	9/7/2022	108 P.M	1 hr		juvenile det- cell b having issues with the door and button	9/8/2022	Tim/Evan
Closed	9/7/2022	113 P.M	1 hr		Juvenile Detention - no power	10/8/2022	Tim L
Closed	10/10/2022	150 Electrical	3 hrs		Juvenile Detention- fire alarm system batteries need to be replaced	10/10/2022	Tim/Evan
Closed	10/10/2022	153 Electrical	5 hrs		juvenile Detention - key pad lock went out	10/14/2022	Tim/Evan
Closed	10/11/2022	155 P.M	1 hr		one of the cells - need sink check out sounds like water running in wall	10/18/2022	Tim/Evan
Closed	10/17/2022	159 Plumbing	2 hrs		Juvenile Det- laundry room dryer	10/18/2022	Tim/Evan
Closed	10/18/2022	222 P.M	2 hrs		Juvenile det- fix light	10/18/2022	Tim/Evan
Closed	10/18/2022	224 Electrical	1 hr		juvenile det- having issues with breaker dryer	10/31/2022	Tim/Evan
Closed	11/1/2021	193 Electrical	2 hrs		Juvenile Det- no power	11/3/2022	Tim/Evan
Closed	11/3/2022	195 Electrical	3 hrs		juvenile detention - kellee's office overhead light is out	11/22/2022	Tim/Evan
Closed	11/17/2022	293 Electrical	1 hr		Juvenile det- lot of lights out	11/27/2022	Tim/Evan
Closed	11/29/2022	319 Electrical	2.5 hrs		fire alarm box is dead- not working (Juvenile Detention)	12/2/2022	Tim/Evan
Closed	12/1/2022	327 Electrical	2 hrs		juvenile det.- tower electrical issues	12/2/2022	Tim/Evan
Closed	12/2/2022	342 Electrical	1.5 hrs		juvenile det- dryer tripped breaker	12/7/2022	Tim/Evan
Closed	12/6/2022	349 Electrical	1.5 hrs		water heater not staying warm for 8 showers - juvenile detention	1/11/2023	Tim/Evan
Closed	12/21/2022	390 Plumbing	2 hrs		plumbing issues - juvenile detention	1/7/2022	Rose
Closed	1/4/2022	502 Plumbing	5 hrs		front gate door hanging to low dragging against the concrete - Justice ce	2/15/2023	Tim/Evan
Closed	2/15/2023	507 P.M	1 hr		need a lock put on that takes a key - juvenile detention	2/21/2023	Tim/Evan
Closed	2/17/2023	512 P.M	1 hr		sink stopped up - juvenile detention	2/27/2023	Tim/Evan
Closed	2/23/2023	529 Plumbing	2 hrs		see kellee- washing machine not working	2/23/2022	Tim/Evan
Closed	2/23/2022	612 Plumbing	2 hrs		juvenile det - washer not working	3/1/2022	Rose
Closed	2/28/2022	621 Plumbing	1.5 hrs		old sheiff's office leak tripping juveniles fire alarm	4/4/2022	Tim L
Closed	3/1/2022	627 Electrical	2 hrs		fixed one faucet - juvenile det	3/9/2023	Tim/Evan
Closed	3/2/2023	539 Plumbing	1 hr		E-B fixed faucets - juvenile det	3/9/2023	Tim/Evan
Closed	3/2/2023	540 Plumbing	1 hr		employee rr fixed faucet - juvenile det	3/9/2023	Tim/Evan
Closed	3/2/2023	541 Plumbing	1 hr		employee rr fixed toilet - juvenile det	3/9/2023	Tim/Evan
Closed	3/2/2023	542 Plumbing	1hr		fixed a/c unit - juvenile det	4/3/2023	Tim/Evan
Closed	3/2/2023	543 Hvac	1 hr		air not working again- juvenile det	3/2/2023	Tim/Evan
Closed	3/2/2023	554 Hvac	1 hr		hot water heater leaking - juvenile det	3/10/2023	Tim/Evan
Closed	3/10/2023	576 Plumbing	1.5 hrs		3 toilets, 2 leaking flush buttons -Juvenile det	3/13/2023	Tim/Evan
Closed	3/13/2023	582 Plumbing	2.5 hrs		help install new TV for the day room - Juvenile Det	3/21/2023	Tim/Evan
Closed	3/17/2023	599 Electrical	1 hr		dryer not working - juvenile det	3/21/2023	Tim/Evan
Closed	3/21/2023	601 P.M	1.5 hrs		install outlet for tv - juvenile det	3/22/2023	Tim/Evan
Closed	3/22/2023	605 Electrical	1 hr		power to the cable box keeps shutting off - juvenile det.	3/23/2023	Tim/Evan
Closed	3/22/2023	609 Electrical	1 hr		toilet is not flushing in one of the cells - juvenile det	3/28/2023	Evan M
Closed	3/23/2023	611 Plumbing	1 hr		hot water heater leaking - juvenile det	4/3/2023	Tim/Evan
Closed	3/24/2023	618 Plumbing	3 hrs		dryer having issues - juvenile det		
Closed	4/3/2023	630 P.M	1 hr				

