

# 650 MAIN ST., BENNINGTON, VT-ROOF REPORT

August 12, 2022



# ROOF LAYOUT Types 1-6



TPO 060 Membrane 1" poly-ISO 1" Built-up ½" Fiberboard Tectum Deck

### Notes:

Roof failing in multiple areas. Improper install. Wet insulation.

#### Roof Type #2



TPO 060 Membrane, 2 Layers of 3"poly-Iso, Wood/Steel Deck

Notes: Improper install. Seams failing. No RPF strip at walls



060 EPDM & TPO 1" Built-up ½" Fiberboard Tectum Deck

Notes:

Roof failing in multiple areas. Improper install. Wet insulation.



TPO 060 Membrane <sup>1</sup>⁄<sub>2</sub>" HD Board <sup>1</sup>⁄<sub>2</sub>" Fiberboard 6" Built-Up Steel Deck

Notes: Roof in good coniodtion.



TPO 060 Membrane <sup>1</sup>/<sub>2</sub>" Fiberboard 1-1/2" Built-up Wood Deck

### Notes:

Improper install- No RPF at walls & curbs not flashed properly. Seams OK.



ROOF TYPE #6- ROOF AT TOP OF PICTURE (MAIN ENTRANCE)

Firestone 090 TPO Membrane 2 Layers of 3" poly-ISO Wood Deck

#### Notes:

Roof in good condition. Field membrane & seams OK. Insulation dry. 30 Yr. Warranty in place.