

RETURN WITH BID

ADDENDUM NO. 1

March 29, 2023

**COUNTY HIGHWAY VARIOUS
2023 PAVEMENT MAINTENANCE – NORTH REGION
SECTION 23-PVMTC-19-GM**

SCHEDULE OF PRICES (DUPAGE COUNTY VERSION OF BLR 12201)

Revised to include alternate bid for work at Mallard Lake Landfill.

SUMMARY OF QUANTITIES

Revised to include alternate bid for work at Mallard Lake Landfill.

SPECIAL PROVISIONS

Add the following to Article 107.27 Insurance.

The Forest Preserve District of DuPage County, its officers and employees shall be named as additional insureds in addition to the County of DuPage.

Add ALTERNATE BIDS, PRE-BID MEETING, and REGRADE ACCESS ROAD special provisions.

A revised Proposal will not be provided, the bidder shall insert the attached documents into the Proposal.

The revised CBID form is available on the DuPage County website at https://www.dupagecounty.gov/_T6_R91.php

By Order of
County of DuPage

(Awarding Authority)

Christopher C. Snyder, P.E.

County Engineer

RETURN WITH BID

Item No.	Items	Unit	Quantity	Unit Price	Total
	BASE BID				
1	SEED BED PREPARATION	SQ YD	3003		
2	SEEDING, CLASS 2A	ACRE	0.62		
3	EROSION CONTROL BLANKET	SQYD	3003		
4	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	55		
5	AGGREGATE WEDGE SHOULDER, TYPE B	TON	60		
6	BITUMINOUS MATERIALS (TACK COAT)	POUND	147814		
7	LONGITUDINAL JOINT SEALANT	FOOT	95240		
8	MIXTURE FOR CRACKS, JOINTS AND FLANGEWAYS	TON	208		
9	POLYMERIZED HOT-MIX ASPHALT BINDER, IL- 4.75, N50	TON	8162		
10	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	3191		
11	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1668		
12	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N70	TON	5221		
13	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, SMA, 9.5, MIX "F", N80	TON	15269		
14	MATERIAL TRANSFER DEVICE	TON	15269		
15	PATH REMOVAL	SQ FT	720		
16	PORTLAND CEMENT CONCRETE SIDEWALK REMOVAL	SQ FT	7935		
17	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	8692		
18	DETECTABLE WARNINGS	SQ FT	1032		
19	HMA SURFACE REMOVAL 1.75"	SQ YD	6267		
20	HMA SURFACE REMOVAL 2.5"	SQ YD	189268		
21	HMA SURFACE REMOVAL 4"	SQ YD	24665		
22	HMA SURFACE REMOVAL - BUTT JOINT	SQ YD	1398		
23	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	12600		

RETURN WITH BID

Item No.	Items	Unit	Quantity	Unit Price	Total
24	TEMPORARY STONE	TON	80		
25	CLASS D PATCHES, TYPE I , 12"	SQ YD	70		
26	CLASS D PATCHES, TYPE II, 12"	SQ YD	210		
27	CLASS D PATCHES, TYPE III, 12"	SQ YD	210		
28	CLASS D PATCHES, TYPE IV, 12"	SQ YD	70		
29	CLASS D PATCHES, TYPE I , 13"	SQ YD	143		
30	CLASS D PATCHES, TYPE II, 13"	SQ YD	427		
31	CLASS D PATCHES, TYPE III, 13"	SQ YD	427		
32	CLASS D PATCHES, TYPE IV, 13"	SQ YD	143		
33	CLASS D PATCHES, TYPE I , 15"	SQ YD	47		
34	CLASS D PATCHES, TYPE II, 15"	SQ YD	142		
35	CLASS D PATCHES, TYPE III, 15"	SQ YD	142		
36	CLASS D PATCHES, TYPE IV, 15"	SQ YD	47		
37	DRAINAGE STRUCTURE TO BE RECONSTRUCTED	EACH	3		
38	DRAINAGE STRUCTURE TO BE REMOVED	EACH	5		
39	INLET TY. A	EACH	5		
40	FRAME AND LIDS, TYPE 1	EACH	25		
41	FRAMES AND GRATES, TYPE 24	EACH	2		
42	FRAMES AND GRATES, TYPE 11	EACH	1		
43	DRAINAGE STRUCTURE TO BE ADJUSTED	EACH	111		
44	DRAINAGE STRUCTURE CLEAN AND PATCH	EACH	28		
45	FRAMES AND LIDS TO BE ADJUSTED, SPECIAL	EACH	69		
46	SHORT TERM PAVEMENT MARKING	FOOT	19567		
47	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	3847		

RETURN WITH BID

Item No.	Items	Unit	Quantity	Unit Price	Total
48	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	76802		
49	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	13568		
50	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	3122		
51	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	8504		
52	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	2091		
53	MODIFIED URETHANE PAVEMENT MARKING - RAISED MEDIAN	SQ FT	2252		
54	TEMPORARY PAINT PAVEMENT MARKING - LETTERS & SYMBOLS	SQ FT	1924		
55	TEMPORARY PAINT PAVEMENT MARKING - LINE 4"	FOOT	353876		
56	TEMPORARY PAINT PAVEMENT MARKING - LINE 24"	FOOT	4182		
57	RECESSED REFLECTIVE PAVEMENT MARKER	EACH	2513		
58	DETECTOR LOOP REPLACEMENT	FOOT	4450		
59	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	9		
60	HANDHOLE TO BE ADJUSTED	EACH	1		
61	RELOCATE EXISITNG PEDESTRIAN PUSH BUTTON	EACH	24		
62	TRAFFIC CONTROL & PROTECTION	L SUM	1		
63	CHANGEABLE MESSAGE SIGN	CAL DAY	140		
64	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1		
65	RAILROAD FLAGGING	DOLLAR	5000	1.00	5,000.00
66	EMERGENCY POTHOLE PATCHING	DOLLAR	20000	1.00	20,000.00
67	REGRADE ACCESS ROAD	SQ YD			
Bidder's Total Proposal (BASE BID)					

RETURN WITH BID

Item No.	Items	Unit	Quantity	Unit Price	Total
	BASE PLUS ALTERNATE				
1	SEED BED PREPARATION	SQ YD	3003		
2	SEEDING, CLASS 2A	ACRE	0.62		
3	EROSION CONTROL BLANKET	SQYD	3003		
4	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	55		
5	AGGREGATE WEDGE SHOULDER, TYPE B	TON	60		
6	BITUMINOUS MATERIALS (TACK COAT)	POUND	147814		
7	LONGITUDINAL JOINT SEALANT	FOOT	95240		
8	MIXTURE FOR CRACKS, JOINTS AND FLANGEWAYS	TON	208		
9	POLYMERIZED HOT-MIX ASPHALT BINDER, IL- 4.75, N50	TON	8162		
10	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	3191		
11	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1668		
12	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N70	TON	5221		
13	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, SMA, 9.5, MIX "F", N80	TON	15269		
14	MATERIAL TRANSFER DEVICE	TON	15269		
15	PATH REMOVAL	SQ FT	720		
16	PORTLAND CEMENT CONCRETE SIDEWALK REMOVAL	SQ FT	7935		
17	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	8692		
18	DETECTABLE WARNINGS	SQ FT	1032		
19	HMA SURFACE REMOVAL 1.75"	SQ YD	6267		
20	HMA SURFACE REMOVAL 2.5"	SQ YD	189268		
21	HMA SURFACE REMOVAL 4"	SQ YD	24665		
22	HMA SURFACE REMOVAL - BUTT JOINT	SQ YD	1398		
23	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	12600		

RETURN WITH BID

Item No.	Items	Unit	Quantity	Unit Price	Total
24	TEMPORARY STONE	TON	80		
25	CLASS D PATCHES, TYPE I , 12"	SQ YD	70		
26	CLASS D PATCHES, TYPE II, 12"	SQ YD	210		
27	CLASS D PATCHES, TYPE III, 12"	SQ YD	210		
28	CLASS D PATCHES, TYPE IV, 12"	SQ YD	70		
29	CLASS D PATCHES, TYPE I , 13"	SQ YD	143		
30	CLASS D PATCHES, TYPE II, 13"	SQ YD	427		
31	CLASS D PATCHES, TYPE III, 13"	SQ YD	427		
32	CLASS D PATCHES, TYPE IV, 13"	SQ YD	143		
33	CLASS D PATCHES, TYPE I , 15"	SQ YD	47		
34	CLASS D PATCHES, TYPE II, 15"	SQ YD	142		
35	CLASS D PATCHES, TYPE III, 15"	SQ YD	142		
36	CLASS D PATCHES, TYPE IV, 15"	SQ YD	47		
37	DRAINAGE STRUCTURE TO BE RECONSTRUCTED	EACH	3		
38	DRAINAGE STRUCTURE TO BE REMOVED	EACH	5		
39	INLET TY. A	EACH	5		
40	FRAME AND LIDS, TYPE 1	EACH	25		
41	FRAMES AND GRATES, TYPE 24	EACH	2		
42	FRAMES AND GRATES, TYPE 11	EACH	1		
43	DRAINAGE STRUCTURE TO BE ADJUSTED	EACH	111		
44	DRAINAGE STRUCTURE CLEAN AND PATCH	EACH	28		
45	FRAMES AND LIDS TO BE ADJUSTED, SPECIAL	EACH	69		
46	SHORT TERM PAVEMENT MARKING	FOOT	19567		
47	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	3847		

RETURN WITH BID

Item No.	Items	Unit	Quantity	Unit Price	Total
48	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	76802		
49	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	13568		
50	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	3122		
51	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	8504		
52	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	2091		
53	MODIFIED URETHANE PAVEMENT MARKING - RAISED MEDIAN	SQ FT	2252		
54	TEMPORARY PAINT PAVEMENT MARKING - LETTERS & SYMBOLS	SQ FT	1924		
55	TEMPORARY PAINT PAVEMENT MARKING - LINE 4"	FOOT	353876		
56	TEMPORARY PAINT PAVEMENT MARKING - LINE 24"	FOOT	4182		
57	RECESSED REFLECTIVE PAVEMENT MARKER	EACH	2513		
58	DETECTOR LOOP REPLACEMENT	FOOT	4450		
59	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	9		
60	HANDHOLE TO BE ADJUSTED	EACH	1		
61	RELOCATE EXISITNG PEDESTRIAN PUSH BUTTON	EACH	24		
62	TRAFFIC CONTROL & PROTECTION	L SUM	1		
63	CHANGEABLE MESSAGE SIGN	CAL DAY	140		
64	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1		
65	RAILROAD FLAGGING	DOLLAR	5000	1.00	5,000.00
66	EMERGENCY POTHOLE PATCHING	DOLLAR	20000	1.00	20,000.00
67	REGRADE ACCESS ROAD	SQ YD	8400		
Bidder's Total Proposal (BASE PLUS ALTERNATE)					

SUMMARY

Bidder's Total Proposal (BASE BID)				
Bidder's Total Proposal (BASE PLUS ALTERNATE)				

1. Each pay item should have a unit price and a total price.
2. If no total price is shown or if there is a discrepancy between the product of the unit price multiplied by the quantity, the unit price shall govern.
3. If a unit price is omitted, the total price will be divided by the quantity in order to establish a unit price.
4. A bid may be declared unacceptable if neither a unit price or total price is shown.

SUMMARY OF QUANTITIES

ITEM #	PAY ITEM	UNIT	ARMY TRAIL ROAD - WEST	ARMY TRAIL ROAD - EAST	MALLARD LAKE LANDFILL	TOTAL QUANTITY
1	SEED BED PREPARATION	SQ YD	353	2650	0	3003
2	SEEDING, CLASS 2A	ACRE	0.07	0.55	0	0.62
3	EROSION CONTROL BLANKET	SQYD	353	2650	0	3003
4	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	5	50	0	55
5	AGGREGATE WEDGE SHOULDER, TYPE B	TON	0	60	0	60
6	BITUMINOUS MATERIALS (TACK COAT)	POUND	39427	108387	0	147814
7	LONGITUDINAL JOINT SEALANT	FOOT	32165	63075	0	95240
8	MIXTURE FOR CRACKS, JOINTS AND FLANGEWAYS	TON	56	152	0	208
9	POLYMERIZED HOT-MIX ASPHALT BINDER, IL- 4.75, N50	TON	2414	5748	0	8162
10	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL- 19.0, N90	TON	0	3191	0	3191
11	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	779	889	0	1668
12	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N70	TON	5221	0	0	5221
13	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, SMA, 9.5, MIX "F", N80	TON	0	15269	0	15269
14	MATERIAL TRANSFER DEVICE	TON	0	15269	0	15269
15	PATH REMOVAL	SQ FT	0	720	0	720
16	PORTLAND CEMENT CONCRETE SIDEWALK REMOVAL	SQ FT	600	7335	0	7935
17	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	600	8092	0	8692
18	DETECTABLE WARNINGS	SQ FT	40	992	0	1032
19	HMA SURFACE REMOVAL 1.75"	SQ YD	3649	2618	0	6267
20	HMA SURFACE REMOVAL 2.5"	SQ YD	55977	133291	0	189268
21	HMA SURFACE REMOVAL 4"	SQ YD	0	24665	0	24665
22	HMA SURFACE REMOVAL - BUTT JOINT	SQ YD	243	1155	0	1398
23	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1600	11000	0	12600
24	TEMPORARY STONE	TON	20	60	0	80
25	CLASS D PATCHES, TYPE I , 12"	SQ YD	70	0	0	70
26	CLASS D PATCHES, TYPE II, 12"	SQ YD	210	0	0	210
27	CLASS D PATCHES, TYPE III, 12"	SQ YD	210	0	0	210
28	CLASS D PATCHES, TYPE IV, 12"	SQ YD	70	0	0	70
29	CLASS D PATCHES, TYPE I , 13"	SQ YD	0	143	0	143
30	CLASS D PATCHES, TYPE II, 13"	SQ YD	0	427	0	427
31	CLASS D PATCHES, TYPE III, 13"	SQ YD	0	427	0	427
32	CLASS D PATCHES, TYPE IV, 13"	SQ YD	0	143	0	143
33	CLASS D PATCHES, TYPE I , 15"	SQ YD	0	47	0	47
34	CLASS D PATCHES, TYPE II, 15"	SQ YD	0	142	0	142
35	CLASS D PATCHES, TYPE III, 15"	SQ YD	0	142	0	142
36	CLASS D PATCHES, TYPE IV, 15"	SQ YD	0	47	0	47
37	DRAINAGE STRUCTURE TO BE RECONSTRUCTED	EACH	1	2	0	3
38	DRAINAGE STRUCTURE TO BE REMOVED	EACH	2	3	0	5
39	INLET TY. A	EACH	2	3	0	5
40	FRAME AND LIDS, TYPE 1	EACH	3	22	0	25
41	FRAMES AND GRATES, TYPE 24	EACH	0	2	0	2
42	FRAMES AND GRATES, TYPE 11	EACH	0	1	0	1
43	DRAINAGE STRUCTURE TO BE ADJUSTED	EACH	20	91	0	111
44	DRAINAGE STRUCTURE CLEAN AND PATCH	EACH	2	26	0	28
45	FRAMES AND LIDS TO BE ADJUSTED, SPECIAL	EACH	3	66	0	69
46	SHORT TERM PAVEMENT MARKING	FOOT	6913	12654	0	19567
* 47	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1118	2729	0	3847
* 48	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	27253	49549	0	76802

* Denotes specialty item

2023 PAVEMENT MAINTENANCE
NORTH REGION
SEC. 23-PVMT-19-GM

ITEM #	PAY ITEM	UNIT	ARMY TRAIL ROAD - WEST	ARMY TRAIL ROAD - EAST	MALLARD LAKE LANDFILL	TOTAL QUANTITY
* 49	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3633	9935	0	13568
50	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	418	2704	0	3122
* 51	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1970	6534	0	8504
* 52	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	533	1558	0	2091
* 53	MODIFIED URETHANE PAVEMENT MARKING - RAISED MEDIAN	SQ FT	0	2252	0	2252
54	TEMPORARY PAINT PAVEMENT MARKING - LETTERS & SYMBOLS	SQ FT	559	1365	0	1924
55	TEMPORARY PAINT PAVEMENT MARKING - LINE 4"	FOOT	121792	232084	0	353876
56	TEMPORARY PAINT PAVEMENT MARKING - LINE 24"	FOOT	1066	3116	0	4182
* 57	RECESSED REFLECTIVE PAVEMENT MARKER	EACH	840	1673	0	2513
* 58	DETECTOR LOOP REPLACEMENT	FOOT	3579	871	0	4450
* 59	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2	7	0	9
* 60	HANDHOLE TO BE ADJUSTED	EACH	0	1	0	1
* 61	RELOCATE EXISTING PEDESTRIAN PUSH BUTTON	EACH	6	18	0	24
62	TRAFFIC CONTROL & PROTECTION	L SUM	-	-	-	1
63	CHANGEABLE MESSAGE SIGN	CAL DAY	28	112	0	140
64	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	0	0	1
65	RAILROAD FLAGGING	DOLLAR	5000	0	0	5000
66	EMERGENCY POTHOLE PATCHING	DOLLAR	-	-	-	20000
67	REGRADE ACCESS ROAD	SQ YD	0	0	8400	8400

* Denotes Specialty Item

ALTERNATE BIDS

This proposal contains a Base Bid and an Alternate Bid. The Base Bid includes the following two (2) locations: Army Trail Road – County Farm Rd to 84 Ct. and Army Trail Road – Schmale Rd to IL 53. The Alternate Bid includes the Base Bid locations AND one (1) additional location: Mallard Lake Landfill. The bidder shall bid on both the Base Bid and Base plus Alternate. The unit prices for Pay Items number one (1) through sixty-six (66) shall be the same for the Base Bid and the Base Plus Alternate.

Add the following to the section for Consideration of Proposals of the BIDDING REQUIREMENTS AND CONDITIONS FOR CONTRACT PROPOSALS (LRS Check Sheet # 6): “The Awarding Authority, at its sole discretion, may award a contract based on either the Base Bid OR the Base plus Alternate Bid in the best interest of the Awarding Authority and budgetary considerations.”

PRE-BID MEETING

An optional pre-bid meeting to view the Mallard Lake Landfill project location will be held on Tuesday April 4, 2023 at 10 a.m. The meeting will be held at 26W580 Schick Road, Hanover Park, IL 60133. Attendees should meet in the cul-de-sac outside the main gate just north of Schick Road at the southwest corner of the landfill.

REGRADE ACCESS ROAD

Description. This work shall consist of furnishing HMA millings, placing, and compacting them in a three (3) inch nominal lift to regrade and smooth the access road that traverses the top of the Mallard Lake Landfill. This work may also include regrading of isolated locations along the ring road around the base of the Mallard Lake Landfill.

Construction Requirements. The HMA millings shall be furnished from the Army Trail Road project locations. Compaction of the millings shall be to the satisfaction of the Engineer.

Basis of Payment. This work will be paid for at the contract unit price per SQ YD for REGRADE ACCESS ROAD, which price shall be payment in full for all labor, equipment, and materials necessary to complete the work as specified.