



---

PO Box 469 \* East Middlebury, VT \* 05740 \* 802.388.1431

December 26, 2022

Town of Middlebury  
1020 South Rt 7  
Middlebury, Vermont 05753

**Project Description:** To Provide and install mechanical equipment (heat pumps, and ERV's), with associated ductwork, controls, power and piping in the storage and basement spaces of the Middlebury Police Department storage building as specified in the drawings titled MPD MEP Drawings VIA Rev 2022-06-13. With exception of upgrade from standard heat pump to hyper heat pump system. The project will also include two (2) additional 20-amp breakers with two grounded outlets on each breaker, to be in the basement for sump pumps, trickle charger, and dehumidifier.

**Includes the following:**

- 1-Mitsubishi MXC-2C20NAHZ 18,000 Btu hyper heat pump outdoor unit
- 2-Mitsubishi MSZ-FS09NA 9,000 Btu wall mounted indoor unit
- 2-Renewaire EV200 Energy recovery ventilator
- Ductwork
- Wall mounted supply grilles
- Wall mounted exhaust grilles
- 300-pound rated wall bracket
- Conduit and wire to provide required electrical system per NEC
- State of Vermont electrical work notice and inspection
- All other necessary material and labor to complete the above project

**Project Cost:** \$46,200.00

**Notes:**

- 1- Substitute wall bracket for ground stand for the heat pump outdoor unit
- 2- Substitute hyper heat pump for standard heat pump

Respectfully submitted by:

Accepted By: \_\_\_\_\_  
Print Name

Dennis M. Newton

\_\_\_\_\_  
Signature Date