TOWN OF MIDDLEBURY VERMONT

77 MAIN STREET, MIDDLEBURY VT 05753

BID FORM

FOR

HAROLD CURTIS BASKETBALL COURT

Bid Number #20181015-1

BID ITEM:

Basketball Court Replacement: Price: $42,095.00 (*)

The Town of Middlebury, Vermont reserves the right to waive any informalities in, or reject any and all bids, to make a partial bid award, or accept any bid deemed to be in the best interest of the Town of Middlebury.

I have inspected all locations, bid specifications and drawings and completely understand this Contract and hereby agree to perform said work at the above Bid Price.

Angela Achin
SIGNATURE

12-13-18
DATE

Vermont Recreational
COMPANY

PO Box 147 Barnet, VT 05821
ADDRESS

800-639-8071
PHONE

(*) PRICE IS BASED ON TOWNS WRITTEN SPECIFICATIONS - PLEASE ATTACHED PROPOSAL FOR VERMONT RECREATIONAL'S RECOMMENDATIONS ON COST SAVINGS.

TOWN OF MIDDLEBURY

Bid Information for

Harold Curtis Park - Basketball Court Replacement

ALL WORK TO BE PERFORMED IN ACCORDANCE WITH THESE SPECIFICATIONS AND AS DETAILED ON THE PLAN TITLED "EAST MIDDLEBURY RECREATION PARK, HAROLD CURTIS PARK BASKETBALL COURT REPLACEMENT, EAST MIDDLEBURY, VERMONT" DATED 3/27/18.

Site Preparation

- Remove existing basketball court asphalt and standards. Dispose of material offsite at Town of Middlebury Resource Park located on Seymour Street Extension
- Existing base material to be re-graded to provide a sub-base a minimum of 10" below proposed finished grade. Unsuitable material shall be removed from the site and replaced with compacted fill material as approved by the Town
- Base material should be a minimum of 6 inches of compacted crushed gravel
- Fine Graded area to be 94' x 58' with a 2% slope on all sides
- Prepare sidewalk areas to drawing specifications (Bituminous Concrete Sidewalk Detail)

Asphalt Layer

- Pave area of 94' by 58' with a 2-1/2" base course bituminous concrete type 2 and 1-1/2 inch of top course bituminous concrete type 4
- Top Course paving shall be placed within 24 hours of base course
- Pave sidewalk areas to drawing specifications ((Bituminous Concrete Sidewalk Detail)
- Supply and install two new, adjustable basketball standards including heavy duty poles, backboards and rims (must submit specs for Town approval)

Playing Surface

- Clean new surface with compressed air
- Apply one coat of acrylic resurfacer
- Apply at least 2 coats of plexipave material, 1st coat should be a texture coat and top coat should have proper amount of pigment to provide a long lasting surface

Marking Lines

- Supply and install complete set of 2 inch white basketball lines per manufactures recommendations

Fencing

- Install 8' high chain link fence along western side of court (70 linear feet)

Please include all warranties, spec sheets and pricing with your bid.

All work to be completed no later than October 15, 2019.

Proposal

Vermont Recreational

Surfacing & Fencing, Inc.

PO Box 147

Barnet, VT 05821

Toll Free Phone - 800-639-8071

Fax - 603-638-4458

Phone - 603-638-2738

Email:vtrecnh@gmail.com

Date : December 13th, 2018

Submitted to:

Town of Middlebury

Department of Public Works

1020 South Route 7

Middlebury, VT 05753

Job: Harold Curtis Park- Basketball Court Replacement, Bid #20181015-1

We hereby propose to furnish the materials and perform the labor necessary for the completion of:

Single Basketball Court

- *Remove and dispose of existing basketball court asphalt and basketball standards, disposing of material offsite at Town of Middlebury Resource Park, located at Seymour Street Extension*
- *Existing base material will then be re-graded to provide a sub-base a minimum of 10" below proposed finished grade. Unsuitable material will be removed from the site and replaced with compacted fill material as approved by the Town, if needed; base material will be a minimum of 6" of compacted crushed gravel.*
- *Area of 94' x 58' will be lazer graded to a pitch of 1% from side to side and compacted with a vibratory roller to a minimum of 95% STD proctor*
- *Area of sidewalk to be prepared per drawing specifications.*

- *Pave total area of 94'x58' with 2-1/2" of compacted base asphalt course bituminous concrete type 2*
- *Pave total area of 94' x 58' with 1-1/2" compacted top asphalt course bituminous concrete type 4, top course to be placed within 24 hours of base course.*
- *Sidewalks to be paved to drawing specifications*

- *Supply and install 2 – adjustable Goalsetter basketball hoops with acrylic backboard and double rim basketball goal*
- *Hoops to be installed in poured in placed concrete footings, 18" x 48" deep.*

- *Supply and install 8' high chain link fence along western side of court, approx.. 70LF.*

- *Clean total surface with compressed air*
- *Total area to receive one coat of black acrylic resurfacer*
- *Total area to receive two coats of Standard Color *Plexipave material. (Manufactured by California Products Corp. Cambridge, MA 02139). Texture coat to contain the proper amount of sand to provide a tough wearing base. Top coat to contain proper amount of pigment to provide a long lasting and attractive surface.*
- *Supply and install one complete set of 2" wide white textured basketball court lines*
- ***Price $42,095.00***

Options

- *Supply and install a total of 3" of hot asphalt to basketball court, 1-1/2" binder and 1-1/2" top course*
- ***Town may Deduct $3,300.00***

- *Supply and install two Jaypro 4-1/2" schedule 40 gooseneck fixed basketball hoops with fan shaped backboard and double rim goal, in lieu of the adjustable.*
- ***Town may Deduct $1,230.00***

All material is guaranteed to be specified, and the above work to be performed in accordance with the drawings and specifications submitted for above work and completed in a substantial workmanlike manner:

Respectfully Submitted _____

Stephen Shattuck

The above prices specifications and conditions are satisfactory and are hereby accepted.

You are authorized to do the work as specified.

NO RETAINAGE

Payment due within 30 days of invoice

Acceptance of Proposal

Signature _____ *Date:* _____

Payments must be made within 30 days from invoice date. An annual finance charge of 18% will be charged on all invoices over 30 days. You will also be responsible for any collection fees that may occur should the account become delinquent