



Town of Middlebury, Vermont

Request for Quotation

Harold Curtis Park

Basketball Court Replacement

May 2018

TOWN OF MIDDLEBURY, VERMONT

Harold Curtis

Basketball Court Replacement

Project Overview

The Town of Middlebury (Town) is seeking bids for renovation of a basketball court located at Harold Curtiss Park in East Middlebury. This bid packet is broken up into 3 sections, Earth Work, Paving/Lining and Fencing. Please supply pricing on each individual section as well as an overall cost for the entire project. Bid sections may be awarded separately or for the whole project.

Earth Work - Bid A

Site Preparation-

- Remove existing basketball court asphalt and existing hoops, dispose of offsite.
- Existing base material to be re-graded to provide a sub-base a minimum of 10" below proposed finished grade. Unsuitable material shall be removed from the site and replaced with compacted fill material as approved by the Town.
- Base material should be a minimum of 6 inches of compacted crushed gravel
- Fine Graded area to be 94' x 58' with a 2 % slope on all sides
- Prepare sidewalk areas to drawing specifications (Bituminous Concrete Sidewalk Detail)

Paving/Striping - Bid B

Asphalt Layer

- Pave area of 94' by 58' with a 2-1/2" base course bituminous concrete type 2 and 1-1/2 inch of top course bituminous concrete type 4
- Top Course paving shall be placed within 24 hours of base course
- Pave Sidewalk areas to drawing specifications ((Bituminous Concrete Sidewalk Detail)
- Supply and install two new hoop systems including galvanized poles and heavy duty backboards and rims

Playing Surface

- Surface treatment shall be California Products Fortified Plexi-Pave system or equal
- Clean Surface with compressed air
- Apply one coat of acrylic resurfacer
- Apply at least 2 coats of plexipave material, 1st coat should be a texture coat and top coat should have proper amount of pigment to provide a long lasting surface

Marking Lines

- Supply and install complete set of 2 inch white basketball lines per manufactures recommendations

Fencing - Bid C

Fencing

Install 8' high chain link fence along western side of court (70 linear feet)

Please include all warranties, spec sheets and pricing with your bid

Bid packages are due by May 31 and may be delivered via Postal Mail or dropped off at the Town of Middlebury Municipal Offices.

All work to be completed no later than October 15, 2018.