

VICINITY MAP
NOT TO SCALE

SITE NOTES:

- ALL SITE DIMENSIONS ARE TO THE FACE OF CURB, UNLESS OTHERWISE NOTED.
- ROUNDOUT PLANS SHOWN WERE TAKING FROM 75% NCDOT PLANS AND MAY BE SUBJECT TO CHANGE.
- ROADWAY IMPROVEMENTS SHOWN OUTSIDE OF THE NCDOT PROPOSED ROUNDOUT PLANS WERE TAKEN FROM A TECHNICAL MEMORANDUM BY KIMLEY-HORN AND ASSOCIATES, INC. DATED NOVEMBER 6, 2015 BASED ON THEIR TRAFFIC ANALYSIS FOR THE SITE.
- SUBJECT PROPERTY IS NOT LOCATED WITHIN A SPECIAL FLOOD HAZARD ZONE PER NFIP F.I.R.M. MAP NUMBER 3710459000J, EFFECTIVE DATE: MARCH 2, 2009.

GENERAL PROVISIONS:

- DEVELOPMENT OF THE SITE SHALL BE GOVERNED BY THIS ZONING PLAN, DEVELOPMENT STANDARDS, AND THE APPLICABLE PROVISIONS OF THE TOWN OF MINT HILL UNIFIED DEVELOPMENT ORDINANCE (UDO).
- THE SCHEMATIC DEPICTIONS OF THE USES, PARKING AREAS, SIDEWALKS, STRUCTURES AND BUILDINGS, AND OTHER SITE ELEMENTS SET FORTH ON THE ZONING SITE PLAN ARE GRAPHIC REPRESENTATIONS OF THE DEVELOPMENT AND SITE ELEMENTS PROPOSED AND MAY BE ALTERED OR MODIFIED IN ACCORDANCE WITH 8.3.2D AMENDMENT PROCEDURES FOR APPROVED CONDITIONAL DISTRICTS.
- PARKING LAYOUTS AND DRIVEWAYS FOR SURFACE PARKING MAY BE MODIFIED TO ACCOMMODATE FINAL BUILDING LOCATION, SIDEWALKS GENERALLY DEPICTED ON THE ZONING SITE PLAN ARE INTENDED TO REFLECT THE GENERAL PEDESTRIAN CIRCULATION FOR THE DEVELOPMENT BUT THE SPECIFIC LOCATIONS OF SUCH SIDEWALKS MAY BE SUBJECT TO VARIATIONS THAT DO NOT MATERIALLY CHANGE DESIGN INTENT GENERALLY DEPICTED ON THE ZONING SITE PLAN.

PERMITTED USES & DEVELOPMENT AREA LIMITATIONS:

- THE SITE MAY BE DEVELOPED WITH A QUICK SERVICE RESTAURANT WITH DRIVE THROUGH, SIT DOWN RESTAURANT WITH DRIVE THROUGH, BEVERAGE (e.g. COFFEE) WITH DRIVE THROUGH, BANK OR OTHER FINANCIAL INSTITUTION WITH DRIVE THROUGH, WIRELESS, HAIR, NAIL, TANNING, GYM, CHIROPRACTIC, DENTIST, MEDICAL OFFICE, URGENT CARE, DAY CARE FACILITY, OR GENERAL RETAIL WITH UP TO 8,000 SQUARE FEET OF TOTAL GROSS FLOOR AREA.
- USES WITH ACCESSORY DRIVE THROUGH WINDOWS SHALL BE ALLOWED ON THE SITE.

ACCESS NOTES

- SITE WILL HAVE ACCESS, AS GENERALLY DEPICTED ON THE ZONING SITE PLAN, TO IDLEWILD ROAD, MATTHEWS-MINT HILL ROAD, AND HOODS VILLAGE DRIVE.
- THE PETITIONER WILL DEDICATE IN FEE-SIMPLE TO THE NORTH CAROLINA DEPARTMENT OF TRANSPORTATION (NCDOT) RIGHT OF WAY AS GENERALLY SHOWN ON THE ZONING PLAN PENDING COMPENSATION TO BE DETERMINED AND AGREED UPON BY PETITIONER AND NCDOT. THIS RIGHT OF WAY DEDICATION SHALL OCCUR PRIOR TO THE ISSUANCE OF THE CERTIFICATE OF OCCUPANCY FOR THE FIRST BUILDING CONSTRUCTED ON THE SITE.
- THE PLACEMENTS AND CONFIGURATIONS OF VEHICULAR ACCESS POINTS ARE SUBJECT TO ANY MINOR MODIFICATIONS, AS APPROVED BY NCDOT, REQUIRED TO ACCOMMODATE FINAL SITE DEVELOPMENT AND CONSTRUCTION PLANS OR AS REQUIRED FOR APPROVAL BY NCDOT IN ACCORDANCE WITH APPLICABLE PUBLISHED STANDARDS.
- THE ALIGNMENT OF THE INTERNAL VEHICULAR CIRCULATION AND DRIVEWAYS MAY BE MODIFIED BY THE PETITIONER TO ACCOMMODATE CHANGES IN TRAFFIC PATTERNS, PARKING LAYOUTS, AND ANY ADJUSTMENTS REQUIRED FOR APPROVAL BY NCDOT IN ACCORDANCE WITH PUBLISHED STANDARDS.

ARCHITECTURAL STANDARDS

- THE BUILDING MATERIALS USED ON THE PRINCIPAL BUILDINGS CONSTRUCTED ON THE SITE SHALL BE A COMBINATION OF PORTIONS OF THE FOLLOWING: BRICK, STONE, PRECAST STONE, PRECAST CONCRETE, SYNTHETIC STONE, STUCCO, METAL PANELS, AND/OR WOOD. ILLUSTRATIVE BUILDING ELEVATIONS HAVE BEEN INCLUDED AS PART OF THE ZONING PLAN TO REFLECT THE ARCHITECTURAL STYLE AND QUALITY OF THE BUILDING THAT MAY BE CONSTRUCTED ON THE SITE.


BRANDING & SIGNAGE

- NO ADDITIONAL RESTRICTIONS SHALL BE REQUIRED PERTAINING TO BRANDING AND SIGNAGE BEYOND WHAT IS REQUIRED IN THE TOWN OF MINT HILL UDO, PARTICULARLY SECTION 6.5.

UNDISTURBED OPEN SPACE

- COMPLY WITH 8.4.1 UNDISTURBED OPEN SPACE.
 - IT SHALL BE THE RESPONSIBILITY OF THE PROPERTY OWNER TO MAINTAIN ANY SCREENING OR LANDSCAPING REQUIRED BY THIS ORDINANCE.
- LARGE MATURING CANOPY TREES SHALL BE A MINIMUM OF TWO AND ONE-HALF (2 1/2) INCHES IN CALIPER AND EIGHT (8) FEET IN HEIGHT AT PLANTING AND SMALL MATURING UNDESTROYED TREES SHALL BE MINIMUM OF TWO (2) INCHES IN CALIPER AND FIVE (5) FEET IN HEIGHT AT TIME OF PLANTING.

PLANT LEGEND	
TYPE	COMMENTS
TREES	
SMALL MATURING	2" AT TIME OF PLANTING
SMALL MATURING	2" AT TIME OF PLANTING
LARGE MATURING	2" AT TIME OF PLANTING
SHRUBS	
SHRUB	36" MIN. HEIGHT AT TIME OF PLANTING
SHRUB	36" MIN. HEIGHT AT TIME OF PLANTING
SHRUB	36" MIN. HEIGHT AT TIME OF PLANTING



SITE AND DEVELOPMENT DATA	
JURISDICTION	TOWN OF MINT HILL
TAX PARCEL(S)	19501895 & 19501896
SITE ADDRESS	13101 & 13215 IDLEWILD ROAD
ZONING	B-G (CD)
USE CLASSIFICATION	COMMERCIAL
TOTAL SITE AREA	
141,912 SQ. FT. OR 3.26 AC.	
MINIMUM FRONT SETBACK	
50 FEET	
MINIMUM CORNER/SIDE SETBACK	
25 FEET / 15 FEET	
MINIMUM REAR SETBACK	
20 FEET	
REQUIRED PARKING	
RESTAURANT	
1 SP. PER 4 SEATS (MIN.)	
150% OF MIN. (MAX.)	
10% OF MAX. (BICYCLE)	
RETAIL	
33 SP. PER 1,000 SQ.FT. (MIN.)	
5 SP. PER 1,000 SQ.FT. (MAX.)	
10% OF MAX. (BICYCLE)	
OFFICE	
3 SP. PER 1,000 SQ.FT. (MIN.)	
5 SP. PER 1,000 SQ.FT. (MAX.)	
10% OF MAX. (BICYCLE)	
PROPOSED PARKING	
LOT 1	
52 SPACES	
(ASSUMES 140 SEAT	
RESTAURANT, 140/4 =	
35 SPACES (MIN.) &	
53 SPACES (MAX.))	
LOT 2	
27 SPACES	
(ASSUMES 72 SEAT COFFEE	
SHOP, 72/4 = 18 SPACES	
(MIN.) & 27 SPACES (MAX.))	

ENGINEERING

P.O. BOX 551
Alpharetta, GA 30009
Indian Trail, NC 28079
(704) 882-2222
www.eagleonline.net

PRELIMINARY
NOT FOR
CONSTRUCTION

NO.	DATE	BY	ISSUE
1.	07/15/16	JLR	ADDRESS TOWN OF MINT HILL STAFF REVIEW COMMENTS

SRE
SAM'S REAL ESTATE

IDLEWILD ROAD AND
MATTHEWS-MINT HILL ROAD
MINT HILL, NC 28227

SAM'S REAL ESTATE
7935 COUNCIL PLACE, SUITE 102
MATTHEWS, NC 28105

ZONING PLAN	
DESIGNED BY	JLR
CHECKED BY	JHR
DRAWN BY	JLR
DATE	06/06/16
JOB NUMBER	5280
SCALE	AS SHOWN