

Town of Scituate
Invitation to Bid
Concrete Slab/Floor
Bid 20190628-1

The Town of Scituate will receive sealed Bids to install a 30 foot by 30 foot concrete slab/floor at the Scituate Animal Shelter on 106 George Washington Hwy, Clayville, RI 02815.

Sealed Bids will be received by the Owner , no later than July 10, 2019 at 12:00PM at the Office of the Town Clerk, 195 Danielson Pike, North Scituate RI 02857. The Bid must clearly not on the outside of the envelope "Animal Shelter - Concrete Floor".

Interested parties may inspect the site if necessary to further facilitate the submission of their Bid.

Bid specifications accompany this notice.

No Bid may be withdrawn for a period of sixty (calendar) days subsequent to the date of the Bid Opening.

Bidders are required to comply with all State of Rhode Island statutory requirements, including Prevailing Wage requirements.

The successful Bidder will be required to provide a Certificate of Insurance, confirming General Liability and Workers Comp (if required) coverage before the contract is awarded.

The Town of Scituate reserves the right to waive informalities and to reject any and all proposals.

April 26, 2018
Scituate Dog Pound
106 George Washington Highway
North Scituate, RI 02857

Job interior concrete floor slab and exterior walkway.

The following specifications are for the interior concrete floor slab to the new addition overall dimensions 30' x 30' = 900 S.F.

- 1. Complete gravel infill and compact to 95%**
- 2. Install 2" ridged styrofoam thermal barrier frost wall protection cut panels to 2' vertical and 2' horizontal around foundation wall perimeter. Note: all panels to fit flush and tight. (Panels on site).**
- 3. Supply and install a commercial grade vapor barrier over the complete floor area overlap a minimum of 16" and apply tape to all joints material selected (Stego Ind. 15 mil vapor barrier).**
- 4. Pour and finish concrete floor slab at 4" thick overall with 3500 psi concrete mix with fiber mesh included in mix, power trowel finish cut 1 1/4" expansion joints, approximately 90 L.F. Floor slab is to align flush with existing interior floor slab.**
- 5. Exterior walkway dimensions 24 lineal feet x 4' foot in width or 96 S.F. overall. Remove existing soil, apply process gravel and compact to 95% compaction, apply perimeter forms. Pour and finish (3500 psi) mix with fiber mesh included.**

Contractor agrees to abide by all federal and state laws and local ordinances.