

ADDENDUM TO RFP (SCIT041):

REPLACEMENT OF FENCING AROUND THE ATHLETIC FIELD AND BASKETBALL COURT AT BERKANDER FIELD, NORTH SCITUATE, RHODE ISLAND (SCIT041)

1. The following changes or clarifications are being made public related to the replacement of fencing around the **Athletic Field at Berkander Field**, across from North Scituate Elementary School, 46 Institute Lane, North Scituate, Rhode Island:
 - All fabric (fencing) around the Athletic Field shall be a 9-gauge core with an 8-gauge finish.
 - The lower course (section) of the Backstop shall be 6-gauge core with a 5-gauge finish.
 - All piping shall be Schedule 40 or equal diameter.
2. The following changes or clarifications are being made public related to the replacement of fencing around the **Basketball Court at Berkander Field**, across from North Scituate Elementary School, 46 Institute Lane, North Scituate, Rhode Island:
 - All fabric (fencing) around the Basketball Court shall be a 9-gauge core with an 8-gauge finish.
 - All piping shall be Schedule 40 or equal diameter.
3. The Date of RFP submission will be extended to: Friday, October 21, 2022 at 1:00 PM
4. The Date of RFP reading will be extended to: Friday, October 21, 2022 at 1:15 PM